

WATER WELL REPORT

STATE OF OREGON

Math
1867#5-16" casing installed
from 0'-86' to 16"
casing installed from
86'-186'- per well
11/5/82 - JCR

RECEIVED

State Well No.

19546E-4aa

JUL 19 1982

State Permit No.

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name RRYMOND FINDLEYAddress RT 1 BOX 530City OntarioState ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐	Driven ☐	Domestic ☐	Industrial ☐	Municipal ☐
Rotary Mud ☐	Dug ☐	Irrigation ☐	Test Well ☐	Other ☐
☒ Bored ☐		Thermal ☐	Withdrawal ☐	Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☐

16" Diam. from 0 ft. to 250 ft. Gauge 250

16" Diam. from 86 ft. to 318 ft. Gauge 318

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered
below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER

" 200 gal./min. with 140 ft. drawdown after 3 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 85 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☐Well seal—Material used PORTLAND Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 20 in.

Diameter of well bore below seal 16 in.

Number of sacks of cement used in well seal 51 sacks

How was cement grout placed? grout pumpWas pump installed? ☒ No Type HP Depth ft.Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Malheur Driller's well number 2NE 1/4 NE 1/4 Section 4 T. 19S R. 46 W.M.

Tax Lot # Lot Blk Subdivision

Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 280 ft.Static level 245 ft. below land surface. Date 6-14-82

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12Depth drilled 700 ft. Depth of completed well 700 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
SOIL	0	3	
br Clay (sandy)	3	60	
br sand (med)	60	186	
br clay (sandy)	186	290	245
w bearing	290	325	245
br clay	325	357	245
blue clay	357	445	
black sand	445	447	274
blue Clay	447	700	274

Work started 5-20 1982 Completed 6-17 1982Date well drilling machine moved off of well 6-17 1982

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Robert A. Bowman Date 7-15, 1982
(Drilling Machine Operator)Drilling Machine Operator's License No. 1406

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Hyco Hump + Drilling
(Person, firm or corporation) (Type or print)Address Box 351 Vale, Ore[Signed] Glen H. Hyco
(Water Well Contractor)Contractor's License No. 396 Date 7-14, 1982

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion.

SP*12658-690