

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report  
are to be filed with the

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

# WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 225/46E-300

State Permit No. \_\_\_\_\_

## (1) OWNER:

Name TOM BRANNIAN  
Address ADRIAN OREGON

## (2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

## (3) TYPE OF WELL:

Rotary ☐ Driven ☒  
Jetted ☐  
Bored ☐

## (4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐  
Irrigation ☐ Test Well ☐ Other ☐

## (5) CASING INSTALLED:

Threaded ☐ Welded ☒  
6" Diam. from 1 ft. to 80 ft. Gage 14  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_

## (6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used \_\_\_\_\_

Size of perforations \_\_\_\_\_ in. by \_\_\_\_\_ in.  
\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

## (7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name \_\_\_\_\_  
Type \_\_\_\_\_ Model No. \_\_\_\_\_  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

## (8) WELL TESTS:

Drawdown is amount water level is  
lowered below static level

Is a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER  
Yield: 95 gal./min. with 20 ft. drawdown after 4 hrs.

Artesian flow \_\_\_\_\_ g.p.m.  
Temperature of water 67 Depth artesian flow encountered \_\_\_\_\_ ft.

## (9) CONSTRUCTION:

Well seal—Material used Cement  
Well sealed from land surface to 30 ft.  
Diameter of well bore to bottom of seal 10 in.  
Diameter of well bore below seal 6 in.  
Number of sacks of cement used in well seal 9 sacks  
How was cement grout placed? PUMPED IN WITH  
PRESSURE GROUT MACHINE

Was a drive shoe used? ☒ Yes ☐ No Plugs \_\_\_\_\_ Size: location \_\_\_\_\_ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? \_\_\_\_\_ depth of strata \_\_\_\_\_

Method of sealing strata off \_\_\_\_\_

Was well gravel packed? ☐ Yes ☒ No Size of gravel: \_\_\_\_\_

Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

## (10) LOCATION OF WELL:

County MALHEUR Driller's well number \_\_\_\_\_  
SW 1/4 SW 1/4 Section 3 T. 22S R. 46E W.M.  
Bearing and distance from section or subdivision corner \_\_\_\_\_

## (11) WATER LEVEL: Completed well.

Depth at which water was first found 67 ft.  
Static level 50 ft. below land surface. Date 4-28-79  
Artesian pressure \_\_\_\_\_ lbs. per square inch. Date \_\_\_\_\_

## (12) WELL LOG:

Diameter of well below casing 6

Depth drilled 102 ft. Depth of completed well 102 ft.

Formation: Describe color, texture, grain size and structure of materials;  
and show thickness and nature of each stratum and aquifer penetrated,  
with at least one entry for each change of formation. Report each change in  
position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL              | From | To  | SWL |
|-----------------------|------|-----|-----|
| SOIL SANDY            | 0    | 3   |     |
| CLAY BROWN            | 3    | 20  |     |
| CLAY SAND WITH GRAVEL | 20   | 65  | 65  |
| SAND BROWN            | 65   | 67  | 65  |
| CLAY BROWN            | 67   | 86  | 65  |
| GRAVELLY SAND         | 86   | 87  | 50  |
| CLAY BLUE SANDY       | 87   | 102 | 50  |

RECEIVED

DEC 05 1980

WATER RESOURCES DEPT  
SALEM, OREGON

Work started 4-23 1979 Completed 4-28 1979  
Date well drilling machine moved off of well 4-30 1979

## Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.  
Materials used and information reported above are true to my  
best knowledge and belief.

[Signed] Cal Belisle Date 5-15, 1979  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1142

## Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is  
true to the best of my knowledge and belief.

Name HOLLOWAY DRILLING CO  
(Person, firm or corporation) (Type or print)

Address ONTARIO OREGON

[Signed] Max Holloway  
(Water Well Contractor)

Contractor's License No. 16 Date 5-18, 1979