

RECEIVED
JUN 1 1959

WATER WELL REPORT
STATE OF OREGON

WALK
2332

27/38-26 A(1)
3

State Well No. 3

State Permit No. 21127

(1) OWNER:

Name HAROLD HUTCHINSON SALEM, OREGON

Address 1502 14th South

5014 Bridge CANADA

(2) LOCATION OF WELL:

County Malheur Owner's number, if any— 3

NE 1/4 NE 1/4 Section 26 T. 27S R. 38E W.M.

Bearing and distance from section or subdivision corner

990' West of 50' South from
the NE corner of sec. 26-27-38.

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

12" Diam. from 2 ft. to 200' ft. Gage 1/4"

10" Diam. from 197' ft. to 257' ft. Gage 3/16"

" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used STAR

SIZE of perforations 1/4" in. by 1 in.

6,000 perforations from 40' ft. to 198' ft.

15,000 perforations from 198' ft. to 257' ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Slot size Set from ft. to ft.

Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

Was a surface seal provided? ☐ Yes ☐ No To what depth? ft.

Material used in seal—

Did any strata contain unusable water? ☐ Yes ☐ No

Type of water? Depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 34' ft. below land surface Date 12-5-58

Artesian pressure lbs. per square inch Date

Log Accepted by:

[Signed] Harold C. Hutchinson Date Feb. 25, 1959

(Owner)

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? HOLLOWAY DRILLING CO.

Yield: 580 gal./min. with 110 ft. drawdown after 25 hrs.

" " " "

" " " "

Baller test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 50° Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well 12 inches.

Depth drilled 260 ft. Depth of completed well 260 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL	0	2
HARD PAN	2	12
BENTONITE	12	34
CLAY	34	40
SAND GRAVEL WATER	40	46
CLAY & GRAVEL	46	74
BLUE SHALE	74	78
BROWN ROCK	78	81
BLUE SANDY SHALE	81	130
HARD BLUE SHALE	130	158
SAND GRAVEL WATER	158	164
SANDY SHALE	164	185
SANDY GRAVEL WATER	185	195
BLUE SHALE	195	210
GRAVEL IN CLAY	210	250
GRAVEL AND SAND	250	257
LAVA ROCK	257	260

Work started 12-27 1958 Completed 1-25 1959

(13) PUMP:

Manufacturer's Name Berkeley

Type: Turbine H.P. 30 Electric

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Holloway Drilling Co.
(Person, firm, or corporation) (Type or print)

Address ONTARIO CRE

Driller's well number

[Signed] Harry Holloway
(Well Driller)

License No. 16 Date 9-6-25, 1959