

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 27/38-33 P

State Permit No. C-3846

(1) OWNER:

Name TOM. Dewell
Address PRINSTON OREGON

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☒

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

12" Diam. from 0 ft. to 234 ft. Gage 1/4
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used STAR DRILLER
Size of perforations 1 in. by 3/16 in.
1200 perforations from 50 ft. to 75 ft.
2160 perforations from 150 ft. to 195 ft.
480 perforations from 320 ft. to 330 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 50' ft. below land surface Date 9-27-67
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER

Yield: 270 gal./min. with 145 ft. drawdown after 10 hrs.
" " " " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 55° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used BENTONITE

Depth of seal 60' ft.

Diameter of well bore to bottom of seal 16 in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth

Was a drive shoe used? ☒ Yes ☐ No

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County MAHOGANY Driller's well number

SE 1/4 SW 1/4 Section 33 T. 27 R. 38 E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 485' ft. Depth of completed well 485' ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
T.C.P. Soil + CLAY	0	18	
BROWN CLAY	18	55	
GRAVEL MEDIUM	55	57	50
CLAY BROWN	57	95	"
ROCK Red	95	202	"
SAND Red	202	232	"
ROCK Red	232	425	"
CLAY Red	425	485	"

Work started 6-12 1967 Completed 9-11 1967

Date well drilling machine moved off of well 9-12 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Jim Gillmore Date 10-25 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 102

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME HOLLOWAY DRILLING CO
(Person, firm or corporation) (Type or print)

Address CENTARIC CREEK

[Signed] May Holloway
(Water Well Contractor)

Contractor's License No. 11 Date 10-25 1967