

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

RECEIVED

MAR 7 1967

State Well No.

State Permit No.

(1) OWNER:

Name FRANK BALTZOR RANCH
Address JORDAN VALLEY ORE

(2) LOCATION OF WELL:

County MALHEUR Driller's well number
SE 1/4 SE 1/4 Section 17 T. 28 S R. 46 E W.M.
Bearing and distance from section or subdivision corner
360' West of East line and 684 ft
North of South line

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

16" Diam. from 0 ft. to 80 ft. Gage 1/4"
" Diam. from " ft. to " ft. Gage "
" Diam. from " ft. to " ft. Gage "

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
in. Slot size _____ Set from _____ ft. to _____ ft.
Diam. Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal CEMENT
Depth of seal 80' ft. Was a packer used? NO
Diameter of well bore to bottom of seal 20 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level _____ ft. below land surface Date _____
Artesian pressure 3 lbs. per square inch Date 3-3-67

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow APPR 400 g.p.m. Date MAR 3 67Temperature of water 55° Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 13 1/2"Depth drilled 240 ft. Depth of completed well 240 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL	0	4
CLAY BR	4	8
GRAVEL COURSE	8	12
HARD LAVA ROCK	12	16
CLAY BR	16	18
HARD LAVA ROCK	18	223
LAVA ROCK FRACTURE	223	240
WITH SPAMS OF LIGHT		
SANDY CLAY & WHITE ROCK		

THIS WELL WAS PERFORATED TO 20"
TO 80', 16" CASING INSTALLED AND
SO SACK OF CEMENT ABOUT WAS
PUMPED IN BETWEEN CASING
& 20" HOLE

16" FLANGE & PLATE BOLTED TO TOP
OF CASING 12" DISCHARGE PIPE 4'
LONG WELDED TO CASING WITH CAP
BOLTED INTO PLACE TO STOP ARTESIAN
FLOW. 2" NIPPLE WELDED TO TOP
PLATE WITH 2" GATE VALVE WITH
REDUCER FOR PRESSURE GAUGE

Work started JAN 1 1967. Completed FEB 25 1967Date well drilling machine moved off of well MAR 3 1967

(13) PUMP:

NOISE

Manufacturer's Name _____

Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME MC GUIRE DRILLING CO
(Person, firm or corporation) (Type or print)

Address PO BOX 1516 PAVETT IDAHODrilling Machine Operator's License No. 81[Signed] J. G. McGuire
(Water Well Contractor)Contractor's License No. 383 Date MAR 3 1967

(USE ADDITIONAL SHEETS IF NECESSARY)