

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON
within 30 days from the date
of well completion.

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

State Permit No.

Name **Prject Corp.**

Address 14th N Second St. Walla Walla, Was.

New Well ☒ **Deepening** ☐ **Reconditioning** ☐ **Abandon** ☐

If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Rotary ☒	Driven ☐	Domestic ☐	Industrial ☐	Municipal ☐
Cable ☐	Jettied ☐	Irrigation ☒	Test Well ☐	Other ☐
Dug ☐	Bored ☐			

Threaded ☐ Welded ☒

14 " Diam. from Top ft. to 500 ft. Gage 219
 " Diam. from ft. to ft. Gage
 " Diam. from ft. to ft. Gage

Perforated? ☒ Yes ☐ No.

Size of perforations		in. by		in.	
8400	perforations from	200	ft. to	500	ft.
	perforations from		ft. to		ft.
	perforations from		ft. to		ft.
	perforations from		ft. to		ft.
	perforations from		ft. to		ft.

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type **Model No.**
Diam. **Slot size** **Set from** **ft. to** **ft.**
Diam. **Slot size** **Set from** **ft. to** **ft.**

Static level 15 ft. below land surface Date 7/1/70
Artesian pressure _____ lbs. per square inch Date _____

Drawdown is amount water level is lowered below static level

Was a pump test made?	☒ Yes	☐ No	If yes, by whom?	Driller
Yield:	15	gal./min. with	200	ft. drawdown after 10 hrs.
	"		"	"
	"		"	"

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water cold was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION: 24 ft 24 inch . 1/4 Casing

Well seal—Material used 3 1/2 inch

Depth of seal cemented in top 24 ft of well

Diameter of well bore to bottom of seal 24 inch

Were any loose strata cemented off? ☐ Yes ☒ No Depth

Was a drive shoe used? ☐ Yes ☒ No

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4

Gravel placed from top ft. to 500 ft.

County Malhuer

Driller's well number

SW $\frac{1}{4}$ NW $\frac{1}{4}$ Section 3 T. 16 R. 44E N.M.

Bearing and distance from section or subdivision corner

Diameter of well below casing

Depth drilled 500 ft. Depth of completed well 500 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	5	
Sand Med	5	7	
Clay Br	7	32	
Gravel Med	32	55	
Clay Blue	55	87	
Sand Course	87	103	
Clay Blue	103	124	
Sand Course	124	130	
Clay Blue	130	152	
Clay & Course Sand	152	250	
Lava Rock	250	258	
Shale Blue	258	344	
Sand & Gravel	344	371	
Shale Blue	371	394	
Sand Gravel	394	433	
Clay Br	433	460	
Sand Course	460	477	
Clay Br.	477	500	

Work started	May 15	19 70	Completed	July 1	19 70
Date well drilling machine moved off of well			July 15 19 70		

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] H. M. Gurne Date July 18, 1970
(Drilling Machine Operator)

Drilling Machine Operator's License No. 81

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME McGuire Drilling Co
(Person, firm or corporation) (Type or print)

Address Rt 1 Box 151F Payette, Idaho

[Signed] H. A. McGuire
(Water Well Contractor)

Contractor's License No. 383 Date July 15, 1970