

STATE OF OREGON
WATER WELL REPORT
 (as required by ORS 537.765)

RECEIVED

JAN 13 1995

WATER RESOURCES DEPT.

(START CARD) #

52781

9
 MAIH
 3088

180/44E/3366

(1) OWNER:

Name Jerry Baker
 Address 21751 Beach Road
 City Vale State OR Zip 97918

Well Number 52781

(9) LOCATION OF WELL by legal description:

County Malheur Latitude _____ Longitude _____
 Township 8 N or S Range 44 E or W. WM.
 Section 33 NW 1/4 NW 1/4
 Tax Lot _____ Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) East Beach Rd

(2) TYPE OF WORK:

New Well Deepen Recondition Abandon

(3) DRILL METHOD:

Rotary Air Rotary Mud Cable
 Other _____

(4) PROPOSED USE:

Domestic Community Industrial Irrigation
 Thermal Injection Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 500 ft.
 Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12	0	28	grout	0	28	3800 LB
12	28	39	grout	28	39	1600 LB
8	39	500				

How was seal placed: Method A B C D E
 Other pumped from bottom up
 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Casing:	Diameter	From	To	Gauge	Steel		Plastic		Welded		Threaded	
					✓				✓			
	12	1	28	250								
	8	12	40	250								

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS: NONE

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailer Air Flowing Artesian
 Yield gal/min 225 Drawdown _____ Drill stem at 500' Time 3 hrs

Temperature of Water 72° Depth Artesian Flow Found _____
 Was a water analysis done? Yes By whom _____
 Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
 Depth of strata: _____

(10) STATIC WATER LEVEL:

16 ft. below land surface. Date Jan 3 95
 Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 12'

From	To	Estimated Flow Rate	SWL
12	14	20	10
300	400	225	16

(12) WELL LOG:

Ground elevation 70-

Material	From	To	SWL
Tersair	0	4	0
Cemented gravel	4	17	0
gravel	17	18	10
Blue sandstone	18	300	0
Blue sandstone (frag)	300	400	16
Blue Hard Sandstone	400	500	0

Date started 12-5-94 Completed 1-4-95

(unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
 Signed Frank Kelly WWC Number 789
 Date 1-4-95

(bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
 Signed Frank Kelly WWC Number 789
 Date 1-4-95