

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT.
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

Math 005

Math
005

State Well No. 13541E-3/22
State Permit No. _____

(1) OWNER:

Name RESOURCE INVESTMENT INC.
Address P. O. BOX 607 ONTARIO, OREGON 97914
DALE ANDERSON - AGENT

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
 Jetted
 Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

CASING INSTALLED:

Threaded Welded

12" Diam. from 0 ft. to 58 ft. Gage .312
10" Diam. from 0 ft. to 250 ft. Gage .250
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? Yes No.

Type of perforator used _____

Size of perforations in. by in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

_____ pump test made? Yes No If yes, by whom?
Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" " " " " "
" " " " " "
Flow test 50 gal./min. with 300 ft. drawdown after 1 hrs.
Artesian flow 6 g.p.m.
Temperature of water 68 Depth artesian flow encountered 260 ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 250 ft.
Diameter of well bore to bottom of seal 16 in.
Diameter of well bore below seal 12 in.
Number of sacks of cement used in well seal 90 sacks
How was cement grout placed? PRESSURE GROUTED
Was a drive shoe used? Yes No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? Yes No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? Yes No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County MALHEUR Driller's well number _____
SE ¼ SE ¼ Section 31 T. 13 R. 41 W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 260 ft.
Static level 0 ft. below land surface. Date 9/15/80
Artesian pressure 10 lbs. per square inch. Date 9/15/80

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 400 ft. Depth of completed well 400 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL | From | To | SWL |
|--------------------------|------|-----|-----|
| Top Soil | 0 | 4 | |
| Brown Clay | 4 | 40 | |
| Medium Sand & Gravel | 40 | 50 | |
| Sandy Brown Clay | 50 | 145 | |
| Medium Sandstone | 145 | 160 | |
| Soft Fractured Sandstone | 160 | 180 | |
| Brown Clay | 180 | 190 | |
| Soft Sandstone | 190 | 400 | |

RECORDED

SEP 29 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 9/15/80 19 Completed 9/15/80 19
Date well drilling machine moved off of well 9/16/80 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Winifred Page Date 9/16/1980
Drilling Machine Operator
Drilling Machine Operator's License No. 65

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Name PAGE BROTHERS DRILLING
(Person, firm or corporation) (Type or print)
Address RT 2 Box 321 VEG VILLE, OREGON 97918
[Signed] Winifred Page
(Water Well Contractor)
Contractor's License No. 564 Date 9/16/80, 19____