

STATE OF OREGON
WATER WELL REPORT
 (as required by ORS 537.765)

MALH
51082

(START CARD) # 115913

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number L15941
 Name Randy Simmons
 Address 3046 5 th. Ave.
 City Brogan State Or. Zip 97903

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
 Special Construction approval ☐ Yes ☒ No Depth of Completed Well 300 ft.
 Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds	
12	0	18	Bentonite	0	18	1200 lbs.	
8	18	300					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other Dry

Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	+1	19	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

		Method		Material	
From	To	Slot size	Number	Diameter	Tele/pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
30	41 ft.		1 hr.

Temperature of water 59° Depth Artesian Flow Found _____
 Was a water analysis done? ☒ No ☐ Yes By whom _____
 Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
 Depth of strata: 10 ft.

(9) LOCATION OF WELL by legal description:

County Malheur Latitude _____ Longitude _____
 Township 15 S. N or S Range 42 E. E or W. WM.
 Section 24 S.E. 1/4 S.W. 1/4
 Tax Lot 600 Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) 3046 5 th. Ave.
Brogan Or. 97903

(10) STATIC WATER LEVEL:
49 ft. below land surface. Date 11-13-98
 Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
 Depth at which water was first found 270 ft.

From	To	Estimated Flow Rate	SWL
270	280	40 gpm.	49

(12) WELL LOG:
 Ground Elevation _____

Material	From	To	SWL
Soil	0	2	
Brn. gravel brn. sand (med.)	2	7	
Brn. clay (hard)	7	110	
Brn. clay	110	270	
Brn. clay brn. sand (fine)	270	280	49
Blue clay (soft)	280	300	49

RECEIVED

NOV 23 1998

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 11-9-98 Completed 11-16-98

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 130811

Signed _____ Date 11-17-98

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1308

Signed Herbert N. Bowman Date 11-17-98