

RECEIVED  
JUL 1 1961

Math  
528



WATER WELL REPORT

State Well No. 1747-104

File Original and First Copy with the STATE ENGINEER, SALEM, OREGON

STATE OF OREGON

State Permit No. ....

(1) OWNER: Name Jack Mendonza, Address Ontario Oregon

(2) LOCATION OF WELL: County Malheur, SW 1/4 SW 1/4 Section 10, T. 17, R. 47 E.W.M. Well is 50' north of County road and 100' west of house

(3) TYPE OF WORK (check): New Well [X], Deepening [ ], Reconditioning [ ], Abandon [ ]

PROPOSED USE (check): Domestic [ ], Industrial [ ], Municipal [ ], Irrigation [X], Test Well [ ], Other [ ]

(5) TYPE OF WELL: Rotary [ ], Cable [ ], Dug [ ], Driven [ ], Jetted [ ], Bored [ ]

(6) CASING INSTALLED: 12" Diam. from 2 ft. to 32 ft. Gage 1/4"

(7) PERFORATIONS: 6 Torch, 180 perforations from 17 ft. to 32 ft.

(8) SCREENS: Well screen installed [X] Yes [ ] No. Manufacturer's Name, Model No., Slot size

(9) CONSTRUCTION: Was well gravel packed? [X] Yes [ ] No. Gravel placed from 17 ft. to 17 ft. Material used in seal - puddled clay

(10) WATER LEVELS: Static level 7 ft. below land surface Date 7-10-61

(11) WELL TESTS: Drawdown is amount water level is lowered below static level. Was a pump test made? [X] Yes [ ] No. Yield: 380 gal./min. with 43 ft. drawdown after 4 hrs.

(12) WELL LOG: Diameter of well 12" inches. Depth drilled 380 ft. Depth of completed well 380 ft.

MATERIAL	FROM	TO
TOP SOIL	0	6
Clay	6	16
Brown fine sand	16	18
Gravel	18	30
Blue Clay	30	260
Reduced hole to 10" at 165'		
Sand rock	260	310
Sand FINE Grey	310	312
Blue Clay	312	380

Work started June 27 1961 Completed July 10 1961

(13) PUMP: Manufacturer's Name No Pump yet

Well Driller's Statement: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Holloway Drilling Co. Address Ontario Oregon. Driller's well number, [Signed] Max Holloway, License No. 16, Date 7-12 1961