

MALH 53055

53055

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Choir Boys LLC Well Number _____
Name Choir Boys LLC
Address 2680 S. Ter Mile Rd
City Meridian State ID Zip 83442

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 245 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds	
10"	0	27	Bentonite	0	27	16 Sacks	
6"	27	245					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Poured in
Backfill placed from 0 ft. to 27 ft. Material Bentonite
Gravel placed from N/A ft. to N/A ft. Size of gravel N/A

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	0	27	38.5	250	☒	☒	☐
Liner: 4 1/2"	25	245	540		☒	☐	☒

Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 38 1/2'

(7) PERFORATIONS/SCREENS:
☒ Perforations Method Factory
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
85'	105'	.20	650	4.5	N/A	☐	☒
125	145	.20	650	4.5	N/A	☐	☒
165	185	.20	650	4.5	N/A	☐	☒
225	245	.20	650	4.5	N/A	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
6 gpm	100'	230'	1 hr.

Temperature of water 58° Depth Artesian Flow Found N/A

Was a water analysis done? ☐ Yes ☒ No
Did any of the water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Month of data 2007 2007

(9) LOCATION OF WELL by legal description:
County Malheur Latitude N43°42.93' Longitude W117°04.834'
Township 21 X or 46 E or WM
Section 27 SW 1/4 SW 1/4
Tax Lot 7001 Lot N/A Block N/A Subdivision N/A
Street Address of Well (or nearest address) 820 Foxtail Rd
Adrian, OR 97901

(10) STATIC WATER LEVEL:
24 ft. below land surface. Date 1/24/07
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 118'

From	To	Estimated Flow Rate	SWL
118	119	2 gpm	24'
175	176	2 gpm	24'
239	240	2 gpm	24'

(12) WELL LOG:
Ground Elevation 2189'

Material	From	To	SWL
Brown Clay	0'	4'	
Brown Sand	4'	8'	
Brown Sand & Gravel	8'	21'	
Blue Clay	21'	27'	
Blue Clay	27'	33'	
Blue clay	33'	118'	
Crack	118	119	24'
Blue clay	119	125	
Blue clay	125	175	
Crack	175	176	24'
Blue Clay	176	200	
Blue clay	200	239	
Crack	239	240	24'
Blue Clay	240	245	

Date started 01/23/07 Completed 01/24/07

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1677
Signed _____ Date 1-25-07

WATER RESOURCES DEPT
SALEM, OREGON

FIRST COPY - CONSTRUCTOR SECOND COPY - CUSTOMER