

STATE OF OREGON

MALH 53569

WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

WELL LABEL # L 88852

START CARD # 198667

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Owner Well I.D. 88852
 First Name Dave Last Name Zylstra
 Company
 Address 504 N Dike Rd
 City Woodland State WA Zip 98674

(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/Commercial ☐ Livestock ☐ Dewatering ☐ Injection
☐ Thermal ☐ Other

(5) BORE HOLE CONSTRUCTION Special Standard: ☐ Yes (attach copy)
 Depth of Completed Well 31 ft.

BORE HOLE			SEAL				
Dia	From	To	Material	From	To	Amount	6ck3/lbs
10	0	31	Bentonite	0	18	31	1550
6	+2	31					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other from surface

Backfill placed from ft. to ft. Material

Filter pack from 18 ft. to 31 ft. Material pc gravel Size 78

Explosives used: ☐ Yes Type Amount

(6) CASING/LINER

Casing	Linr	Dia	+	From	To	Gauge	Steel	Plastic	Welded	Thrd
X		6"	+	2	31	.250	X		X	

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)

Temporary casing ☒ Yes Diameter 10 From 0+1 To 26

(7) PERFORATIONS/SCREENS

Perforations Method torch

Screens Type Material

Perf	Scrn	Casing	Linr	Screen Dia	From	To	Screen/slot width	Slot length	# of slots	Tele/pipe size
X		X			20	26	1/8	6"	30	6"

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
35 gpm	1 ft	20 ft	2 hrs

Temperature 59 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below)

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Malheur Twp 20S or S Range 47E or W W.M.
 Sec 31 SW 1/4 of the Max Lot 1301
 Tax Map Number Lot

Lat " or DMS or DD
 Long " or DMS or DD

Street Address of Well (or nearest address) Beaumont Rd
 Adrian, OR, Gov Lot 4

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well/Predeepening	7-6-09			
Completed Well				11'-6"

Flowing Artesian? ☐ Yes Dry Hole? ☐ Yes

WATER BEARING ZONES Depth water was first found

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7-6-09	18	26	100 gpm			11'-6"

(11) WELL LOG

Ground Elevation

Material	From	To
top soil	0	6
Bn sandy clay	6	18
med gravel & sand	18	26
Blue clay	26	31
RECEIVED		
SEP 02 2009		
WATER RESOURCES DEPT		
SALEM, OREGON		

Date Started 4-25-09 Completed 7-6-09

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Licensed Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Licensed Number 1485 Date 8-2-09

Signed Jon M Fife

Contact Info. (optional)