

0-60 – Clay gray
 60-65 – Red basalt, gray clay
 65-68 – Clay blue hard, red basalt chips
 68-70 – same
 70-88 – altered basalt (green) pieces of silica and mica
 88-94 – out of basalt, green mud stone
 94-98 – green mudstone, pieces of basalt mixed in
 98-105 – basalt red
 105-108 – basalt black with green mudstone veins
 108-208 – green clay stone, (mudstone) fine grain
 208-225 – basalt black fractures of calcite
 225-240 – basalt fractured silica and calcite streaks
 240-245 – red claystone
 245-255 – red and blue claystone pieces of pyrite and silica
 255-270 – basalt black, little water
 270-290 – basalt black, pyrite
 290-295 – basalt with streaks of light blue and red mud stone
 295-315 – basalt, silica and calcite in fractures
 315-330 – basalt hard
 330-346 – basalt red tint, calcite and silica and pyrite in fractures
 346-371 – black and red basalt, calcite
 371-426 – basalt black, hard
 426-432 – basalt red, calcite and silica
 432-443 – basalt, silica calcite and green mud stone pieces
 443-455 – basalt hard black
 455-457 – basalt, streaks of green mud stone
 457-462 – blue and red mud stone, 90% red
 462-470 – light blue mud stone with sticky light blue clay mixed
 470-484 – *large (1"- 2") red and blue clay stone pieces, soft gray streaks between layers
 484-520 – blue clay stone, soft blue streaks
 520-522 – basalt black, altered –silica crystals inside
 522-545 – basalt with streaks of blue claystone
 545-548 – basalt with streaks of brown claystone
 548-550 – basalt fractured, silica and calcite streaks
 550-570 – basalt fractured, red clay streaks and calcite
 570-600 – red clay, pieces of basalt
 600-610 – basalt, red and blue clay streaks
 610-618 – basalt, oxidized
 618-623 – basalt punky, blue clay streaks
 623-628 – red claystone, red clay streaks
 628-630 – basalt hard, calcite and silica streaks
 630-640 – basalt with streaks of gray clay
 640-643 – red claystone, red clay, basalt chips
 643-655 – basalt hard
 655-670 – basalt punky, gray clay streaks
 670-673 – gray claystone
 673-680 – blue and green claystone streaks
 680-688 – basalt, clay streaks blue/green
 688-718 – basalt punky, clay streaks
 718-745 – red clay, red basalt pieces
 745-761 – basalt, getting harder less punky the further we go
 761-795 – basalt punky, blue clay streaks
 795-800 – basalt, silica streaks
 800-803 – basalt hard, silica streaks
 803-867 – basalt and red clay
 867-875 – basalt, silica, mica and blue clay streaks

RECEIVED BY OWRD

JUN 28 2013

SALEM, OR

L 101319
MALH 54035

875-885 – green and red clay stone
885-905 – oxidized basalt, streaks of blue/green clay
905-924 – basalt streaks of blue/green claystone silica, calcite
924-935 – basalt, green claystone, streaks of soft red clay, calcite
935-940 – oxidized basalt, calcite, silica, soft white
940-952 – basalt, green clay stone, calcite, silica
952-965 – green claystone, streaks of soft red clay
965-970 – oxidized basalt, streaks of red clay, calcite, silica
970-1005 – blue claystone, blue clay with basalt chips
1005-1025 – blue/green claystone, basalt chips, streaks of soft clay
1025-1035 – soft blue clay, some hard streaks of basalt chips and calcite
1035-1300 – basalt, streaks of blue claystone, calcite, silica
1300-1318 – hard basalt calcite, streaks of green claystone
1318-1340 – hard basalt calcite, silica, green claystone
1340-1390 – blue clay and claystone, weathered basalt calcite
1390-1415 – weather basalt chips, hard green claystone, calcite
1415-1442 – blue claystone, blue clay
1442-1460 – basalt hard, green claystone, small calcite
1460-1475 – blue/green clay and some claystone, silica, streaks of basalt
1475-1540 – hard basalt and green claystone, calcite, silica
1540-1565 – basalt calcite, streaks of softy blue clay
1565-1600 – basalt, silica, streaks of brown clay, calcite
1600-1610 – basalt, blue clay, silica, calcite
1610-1615 – hard basalt, blue claystone, calcite
1615-1645 – basalt, blue claystone, increased silica, calcite
1645-1660 – gray claystone
1660-1661 – basalt, green claystone, silica, calcite
1661-1670 – green claystone, silica, calcite, red claystone streaks
1670-1675 – weathered basalt, green claystone, calcite, silica
1675-1705 – hard basalt, green claystone, silica, calcite, mica
1705-1728 – green claystone, streaks of brown and red claystone
1728-1737 – weathered basalt, green claystone, calcite, silica
1737-1818 – basalt, streaks of soft gray clay, calcite, silica
1818-1855 – basalt, calcite, silica
1855-1884 – basalt, green claystone, silica, calcite
1884-1894 – red clay, blue claystone
1894-1905 – gray clay and claystone
1905-1907 – red clay and green claystone
1907-1908 – green claystone, basalt, calcite, silica
1908-1930 – basalt, red brown clay
1930-1960 – clay red, green claystone, little basalt black
1960-1970 – claystone green, some clay gray soft, some small basalt flakes
1970-1978 – claystone green hard, clay gray med/hard
1978-1996 – red claystone, green claystone, small flakes of basalt
1996-2000 – small white flakes, green clay stone, basalt, dark green claystone, ~~claystone~~

RECEIVED BY OWRD

JUN 28 2013

SALEM, OR

