

STATE OF OREGON
WATER SUPPLY WELL REPORT

MALH 54908

WELL I.D. LABEL# L

158980

START CARD #

1081213

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

3/2/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name AIDENLast Name SPIERS

Company _____

Address 1850 HIGHWAY 201City ADRIANState ORZip 97901**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud

☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 281.00 ft.

BORE HOLE			SEAL				sacks/
Dia	From	To	Material	From	To	Amt	lbs
10	0	18	Bentonite Chips	0	18	15	S
6	18	281			Calculated	8.22	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: SLOW POUR

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 2/3/2026 Begin Time 08 00**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount _____

Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	2	32	0.250	ST	☒		OUT.	32
L	4.5		21	281	SDR21	PL		☒		

Temp casing ☐ Yes Dia _____ From + ☐ _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type Certa Lock Material PVC

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	4.5	201	281	.016			Telescope

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	8		260	2

Temperature 58 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 457 mg/L

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County MALHEUR Twp 21.00 S N/S Range 46.00 E E/W WMSec 34 SE 1/4 of the NW 1/4 Tax Lot 5602

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 43.70184000 DMS or DD

Long _____ ° _____ ' _____ " or -117.08838000 DMS or DD

☒ Street address of well ☐ Nearest address1850 HIGHWAY 201, ADRIAN, OR 97901**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	2/6/2026			28
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 40.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
2/3/2026	40	45	1			28
2/4/2026	203	245	2			28
2/5/2026	274	275	5			28

(11) WELL LOGGround Elevation 2211.32 FT

Material	From	To
Top Soil	0	2
Sand	2	14
Brown Clay Sand Strips	14	20
Small Gravel	20	23
Hard Blue Clay	23	203
Blue Clay Cracks	203	245
Hard Blue Clay	245	260
Blue Clay Cracks	260	261
Hard Blue Clay	261	274
Hard Clay Cracks	274	275
Hard Blue Clay	275	281

Construction

Begin Date 2/3/2026 Begin Time 08 00 End Date 2/6/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2137 Date 3/2/2026Signed WES WHITE (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 2137 Date 3/2/2026Signed WES WHITE (E-filed)Drilling Company: Treasure Valley Drilling

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MALH 54908

3/2/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 43.70184000 Datum: WGS84

Longitude: -117.08838000

Township/Range/Section/Quarter-Quarter Section:
WM21.00S46.00E34 SENW

Address of Well:

1850 HIGHWAY 201, ADRIAN, OR 97901

Well Label: 158980

Printed: March 2, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

