

STATE OF OREGON
WATER SUPPLY WELL REPORT

MALH 54948

WELL I.D. LABEL# 152358

START CARD # 1082547

8/21/2026

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

(1) LAND OWNER

Owner Well I.D. _____

First Name TEO Last Name MAESTREJUAN

Company _____

Address 26613 PLEASANT VALLEY RDCity JORDAN VALLEY State OR Zip 97410

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Dia + From To Gauge Stl Plstc Wld Thrd

Casing: _____ Material From To Amt sacks/lbs

Seal: _____

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☐ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☒ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)Depth of Completed Well 400.00 ft.

BORE HOLE			SEAL			Amt	sacks/lbs
Dia	From	To	Material	From	To		
10	0	340	Bentonite Chips	0	190	110	S
6	340	405			Calculated	95	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: SLOW POURBackfill placed from 190 ft. to 305 ft. Material PEA GRAVEL 3/8

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 7/17/2026 Begin Time 10 : 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+ From	To	Gauge	Mat. Type	Wld	Thrd	Shoe Location
C	6	☒ 2	358	0.250	ST	☒		IN 358
L	4.5		300	SDR21	PL		☒	

Temp casing ☒ Yes Dia 10 From + ☐ 0 To 10

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type SDR17Material PVC

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scr/slot width	Slot length	# of slots	Tele/ Pipe size
		4.5	360	400	.02			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	33		380	1

Temperature 56 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 314 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County MALHEUR Twp 31.00 S N/S Range 44.00 E E/W WMSec 15 NE 1/4 of the NW 1/4 Tax Lot 200

Tax Map Number _____ Lot _____

Lat _____ " or 42.87027780 DMS or DDLong _____ " or -117.32027800 DMS or DD☐ Street address of well ☒ Nearest address

OFF THREE FORKS RD, 2.5 MILES SOUTH OF US-95

(10) STATIC WATER LEVEL

	Date	SWL(psi)	+ SWL(ft)
Existing Well / Pre-Alteration			
Completed Well	<u>7/20/2026</u>		<u>300</u>

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 365.00

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
<u>7/9/2026</u>	<u>365</u>	<u>405</u>	<u>33</u>		<u>300</u>

(11) WELL LOG

Ground Elevation 4253.32 FT

Material	From	To
Brown Clay	0	135
Cemented Gravel	135	165
Brown Clay	165	297
Gravels	297	320
Brown Clay	320	365
Brown Clay with Sand Layers	365	405

Construction

Begin Date 7/2/2026 Begin Time 12 : 00 End Date 7/20/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2026 Date 8/20/2026Signed SAMUEL NAVARRO (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1714 Date 8/21/2026Signed DAVID ADAMSON (E-filed)Drilling Company: Adamson Pump & Drilling, Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:
New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MALH 54948

8/21/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 42.87027780 Datum: WGS84

Longitude: -117.32027800

Township/Range/Section/Quarter-Quarter Section:

WM31.00S44.00E15NENW

Address of Well:

OFF THREE FORKS RD, 2.5 MILES SOUTH OF US-95

Well Label: 152358

Printed: August 21, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

