

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

State Well No. 145/42E-6 ad
State Permit No. _____

(1) OWNER:

Name Jack Hostick
Address General Delivery
Brogan, Or. 97903

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
1 ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
10" Diam. from +1 ft. to 14.1 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Factory
Size of perforations 1/8 in. by 3 in.
8 row perforations from 117 ft. to 141 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller
Yield: 38 gal./min. with 25 ft. drawdown after 3 hrs.

" " " "
" " " "

Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water 61 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Portland Cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 14 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 19 sacks
How was cement grout placed? with grout pump

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____
Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Malheur Driller's well number _____
SE ¼ NE ¼ Section 6 T. 14S R. 42E W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 8 ft.
Static level 8 ft. below land surface. Date 7/13/80
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 10"

Depth drilled 250 ft. Depth of completed well 247 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil, medium sand & gravel	0	6	
Clay, brown, small cobbles	6	12	8
Clay, hard, brown	12	30	8
Clay, brown, w/ med. gravel	30	65	8
Gravel, medium, hard	65	75	8
Clay, brown	75	115	8
Sand, medium & gravel, water-bearing	115	137	85
Clay, hard, brown w/ sm. cobbles	137	175	85
Clay, brown	175	250	85

RECEIVED
SEP 10 1980
WATER RESOURCES DEPT
SALEM, OREGON

Work started 7/12 19 80 Completed 8/14 19 80

Date well drilling machine moved off of well 8/14 19 80

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Herbert H. Bowman Date Aug 20, 19____
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1406

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name PIONEER WATER DEVELOPMENT, INC.
(Person, firm or corporation) (Type or print)

Address Rt. 3 Box 493 Ontario, Or. 97914

[Signed] [Signature] (Water Well Contractor)

Contractor's License No. 748 Date 9-5, 1980



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for Well ID Number

RECEIVED

OCT 9 2024

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Ty Sharp (Three Valleys Ranch, LLC)

Mailing Address: 22141 Bridgeport Ln

City, State, Zip: Bridgeport, OR, 97819

Mail Well ID to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)

Name & Address: _____

City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 14 S (North / South) Range: 42 E (East / West) Section: 6 SE 1/4 of the SE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 1200 County Malheur

GPS Coordinates: 44.3727, -117.6115 (verified by Bob Maynard, OWRD well inspector, in 2009)

Street Address of Well, City: Mormon Basin Cutoff Rd (approx 760' W of)

If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Mining

Date Well Constructed (or property built): 8-14-1980 Total Well Depth: 247' Casing Diameter: 10"

Owner at time the well was constructed (if known): Jack Hostick Well Report # (if known): MALH 56

Other Information: Original tag L-95124, attached by Bob Maynard is lost

SUBMITTED BY (please print): Paul Garvin

PHONE: 503-347-7188 EMAIL &/or FAX: garvin.hydrogeo@gmail.com

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301.
Or EMAIL the completed PDF form to: Ladeena.K.Ashley@water.oregon.gov, or FAX it to: (503) 986-0902.

****REPLACEMENT ID****

For Official Use Only by the Oregon Water Resources Department:

Received Date:
10-9-2024

Well Report Number:
MALH 56

Well Identification #:
L-156029

Laurie Norton

From: Bob Maynard
Sent: Monday, November 16, 2009 12:03 PM
To: Laurie Norton
Subject: MALH 056

Hi Laurie, have a little update on a well location that the landowners want. They are applying for water rights out of this well so they want it in the right 1/4. The well is MALH 056 and they show it in the SE of the NE, but it is really in the SE of the SE. I have personally been to the well and not only GPS it, but videoed the well to make sure that it matched the well log, which it does. The well is now owned by Hammond Ranch #2 and is in 14S, 42E, sec 6, SE of SE in tax lot 1200. The GPS is N 44.37270 W -117.61150. If you could include this with the original well log it would be appreciated, if you have any questions please ask, thanks Bob

11/16/2009

For Official Use Only by The Oregon Water Resources Department:

Received Date: _____

County Well Log ID #

Well Identification Tag #

MALH 056

~~L 95124~~ LOST!

RECEIVED

JAN 15 2010

WATER RESOURCES DEPT
SALEM, OREGON

APPLICATION FOR WELL IDENTIFICATION TAG

LANDOWNER INFORMATION

Name: Steve Jay Agent for Three Valleys Ranch

Mailing Address: PO Box 5075

City: Bridgeport State: OR Zip: 97819

Return Well Tag to (if different than mailing address): N/A

WELL LOCATION INFORMATION

County: MALHEUR Township: 14 S North or South (circle one) Range: 42 E East or West (circle one),

Section: 6 SE 1/4 SE 1/4 Tax Lot #: 1200

N 44.37270 W-117.61150
Street Address of Well (if different than mailing address): Mannan Basin Creek

County Road

WELL INFORMATION (Do Not Complete If Well Report is Attached)

Type of Well (i.e. domestic, irrigation, etc): _____ Date Well Constructed: _____

Well Constructor/Company: _____

Well Depth (in feet): _____ Diameter of Well Casing (in inches): _____

Landowner Who Had Well Constructed or Previous Owner at the Time Well was Constructed (if known): _____

*Replaced by
tag well ID#
L 156029*

Other Information: _____

Return to: Oregon Water Resources Department, Janet Halladey, 725 Summer St. NE, Suite A, Salem,
OR 97301-1271, (503) 986-0854 or fax to 503-986-0902

App for tag