

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

State Well No. _____

State Permit No. 85/2W-15

WATER RESOURCES DEPT.

(1) OWNER:

Name Mr. & Mrs. Ray Satterwhite
Address 5655 72nd Ave. S.E., Salem 97301

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 143 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills Knife
Size of perforations 1/4 in. by 2 in.
210 perforations from 142 ft. to 125 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" " " "
"Air lift 20 gpm from 155' after 2 hr."
Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement & aggreg.
Well sealed from land surface to 70 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 16 sacks
Number of sacks of bentonite used in well seal _____ sacks
Brand name of bentonite _____
Number of pounds of bentonite per 100 gallons
of water _____ lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4" rd.
Gravel placed from 143 ft. to 70 ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 864
NW 1/4 SE 1/4 Section 15 T. 8S R. 2W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 100 ft.
Static level 63 ft. below land surface. Date 7/10/76
Artesian pressure _____ lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 156 ft. Depth of completed well 156 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Ton soil	0'	3'	
Claystone (rust red)	3'	15'	
Claystone (orange red)	15'	35'	
Weathered basalt & boulder	35'	70'	
Claystone (orange brown)	70'	95'	
Weathered basalt (brown)	95'	120'	63'
Basalt (broken brown)	120'	140'	63'
Basalt (broken black)	140'	152'	63'
Clay (brown firm)	152'	154'	
Clay (blue firm)	154'	156'	

Work started 7/7/76 19 Completed 7/10/76 19

Date well drilling machine moved off of well 7/10/76 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Pete Tolmasoff Date 7/12/1976
(Drilling Machine Operator)

Drilling Machine Operator's License No. 320

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Pete Tolmasoff Well Drilling
(Person, firm or corporation) (Type or print)

Address Turner, Ore.

[Signed] Pete Tolmasoff
(Water Well Contractor)

Contractor's License No. 410 Date 7/12/76 19