

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 8512W-16

State Permit No. G-8659

(1) OWNER:

Name William Fullhart
Address 6295 AUMSKILL H-WAY
AUMSKILL, ORE 301

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 11 ft. to 82 ft. Gage 1250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " "
" Air " " "
Pump test 30 gal./min. with 53 ft. drawdown after 1 hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 82 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 27 sacks
How was cement grout placed? Air grout Pump

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number
1/4 1/4 Section 16 T. 8S R. 2W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 130 ft.
Static level 183 ft. below land surface. Date 8-21-79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 336 ft. Depth of completed well 336 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	1	
Brown Clay	1	6	
Red Clay	6	21	
Tan Clay	21	30	
Tan Clay Sandy	30	38	
Gray Clay Sandy	38	72	
Blue Gray Shale	72	103	
Gray Shale	103	215	
Multi-Colored Shale	215	224	
Light Gray Sandstone	224	270	
Gray Sandstone	270	285	
White Claystone	285	306	
Light Gray Sandstone	306	336	183'

RECEIVED

FEB 19 1980

WATER RESOURCES DEPT.

SALEM, OREGON

Work started 8-17 1979 Completed 8-21 1979
Date well drilling machine moved off of well 8-21 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] J.D. Monders Date 8-21, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1195

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Miller West Well Drilling
(Person, firm or corporation) (Type or print)

Address 5875 Gaffin Rd. Salem

[Signed] Marc Monders
(Water Well Contractor)

Contractor's License No. 746 Date 8-21, 1979