

Henry Hazenberg

Material	From	To
Top soil	0	2
Clay, light brown silty soft	2	43
Clay, light brown silty medium	43	53
Clay, light brown silty soft	53	61
Clay, light green silty soft	61	64
Clay, greenish brown gritty & sandy soft	64	67
Clay, gray gritty soft	67	69
Clay, Green & gray gritty soft	69	71
Clay, gray sandy medium	71	74
Sand stone, green soft	74	75
Clay, green & brown w/ green sand	75	78
Gravel, $\frac{3}{8}$ " w/ sand, green & gray coarse	78	79
Gravel w/ clay, brown	79	81
Clay, green & sand, fine	81	88
Gravel & sand, coarse	88	89
Clay, brown soft	89	123
Gravel & sand, coarse	123	124
Clay, green medium	124	130
Clay, green & brown medium	130	147
Clay, green medium	147	175
Clay, green hard sticky	175	200
Gravel w/ clay, green	200	202
Clay, green hard & sticky	202	223
Clay, green soft & sticky	223	227
Clay, green w/ grit	227	245
Clay, green & brown w/ grit	245	249
Clay, gray hard	249	251
Clay, green silty soft	251	258
Clay, green & sand, fine soft	258	259
Clay, green & sand, fine hard	259	261
Clay, green gritty	261	262
Clay, green & sand, fine	262	264
Sand, black coarse	264	267
Sand & gravel $\frac{1}{2}$ "	267	269
Clay, green sandy	269	270
Sand, black medium to fine	270	275
Sand, medium	275	276
Sand, coarse & clay, gray	276	279
Clay, green hard	279	281
Clay, blue gray gritty soft	281	287
Clay, green hard	287	295
Clay, green gritty	296	297
Clay, sandy & sand, fine	297	300
Sand, black medium	300	302
Sand, coarse	302	303
Clay, gray hard	303	308
Clay, gritty	308	316
Clay, hard green	316	324

Henry Hazenberg

CASING INSTALLED:

16" Diam. from	+3 ft	to	117' 1 3/4 "	Gage	.250
16" Diam. from	117' 13/4"	to	136' 6 1/4"	Gage	.375
16" Diam. from	136' 6 1/4"	to	196' 6"	Gage	.250
16" Diam. from	196' 6"	to	215' 10 1/2"	Gage	.375
16" Diam. from	215' 10 1/2"	to	255' 9 3/4"	Gage	.250
16" Diam. from	255' 9 3/4"	to	318' 7 7/8"	Gage	.375
16" Diam. from	318' 7 7/8"	to	338' 8 3/4"	Gage	.250
6" Diam. from	+1'	to	39' (gravel feed)		