

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MARI.....

PLEASE TYPE or PRINT IN INK

RECEIVED

NOV 26 1984

WATER RESOURCES DEPT (for official use only)

(1) OWNER:

Name Randy & Beckie Jackson
Address 3210 Abrams Street NE
City Salem, Ore. 97302 State Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐
☐ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☐
6" Diam. from 1 ft. to 20 ft. Gauge .250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☐
" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
gal./min. with ft. drawdown after hrs.
Air test 20 gal./min. with drill stem at 360 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used Cement
Well sealed from land surface to 19 ft.
Diameter of well bore to bottom of seal 8 in.
Diameter of well bore below seal 6 in.
Amount of sealing material 2 1/2 sacks ☒ pounds ☐
How was cement grout placed? method B
Was pump installed? no Type HP Depth ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION AND legal description:

County Marion NW 1/4 SE 1/4 of Section 21 of
Township 8S Range 2W WM.
(Township is North or South) (Range is East or West)
Tax Lot Lot Block Subdivision
MAILING ADDRESS OF WELL (or nearest address) Witzel Road -6622

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 327 ft.
Static level 153 ft. below land surface. Date 11/21/84
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"
Depth drilled 360 ft. Depth of completed well 360 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0'	1'	
Clay (red brown)	1'	7'	
Claystone (yellow tan)	7'	12'	
Shale (hard dark)	12'	40'	
Shale (tuffy grey)	40'	45'	
Shale (tuffy lavender)	45'	50'	
Shale (dark hard)	50'	160'	
Shale (embedded gravel small)	160'	170'	
Shale (tuffy blue grey grainy)	170'	270'	
Shale (hard dark gritty)	270'	300'	
Shale (grey blue gritty)	300'	310'	
Shale (grey green sandy)	310'	340'	153'
Shale (dark hard sandy)	340'	360'	153'

Date work started 11/19/84 /completed 11/22/84
Date well drilling machine moved off of well 11/22/84 19

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Peter J Tolmasoff Date 11/23, 19 84

(bonded) Water Well Constructor Certification:

Bond 2035392 Issued by: Western Surety Co.
(number) (Surety Company Name)
On behalf of Peter J Tolmasoff
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Peter J Tolmasoff
(Water Well Constructor)
(Dated) 11/23/84

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690