

WATER WELL REPORT
STATE OF OREGON

MAR 11 1984

RECEIVED

NOV 2 1983

State Well No.

89/2W-30

State Permit No.

PLEASE TYPE OR PRINT IN INK
WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name JIM PEEPLES
Address 7621 TERAL CT.
City SALEM State ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
☐ Bored ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☒ Welded ☒
....." Diam. from 0.75 ft. to 30 ft. Gauge 2.88
....." Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

....." Diam. from 2 ft. to 352 ft. Gauge 1.60 lb.

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used saw
Size of perforations 1/8 in. by 6 in.
72 perforations from 270 ft. to 350 ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.
Air test 28-30 gal./min. with drill stem at 340 ft. 2 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used cement
Well sealed from land surface to 29 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 10 sacks
How was cement grout placed? pumped

Was pump installed? Type HP Depth ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/4
Gravel placed from 290 ft. to 350 ft.

(10) LOCATION OF WELL:

County Marion Driller's well number
Tax Lot # 1/4 Section 30 T. 8S R. 2W W.M.
Address at well location: 7621 Teral Ct Salem

(11) WATER LEVEL: Completed well.

Depth at which water was first found 160 ft.
Static level 127 ft. below land surface. Date 10-19
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 352 ft. Depth of completed well 352 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	1	
Clay (orange)	1	23	
Clay stone (grey)	23	50	
Sand Stone (Gray)	50	70	
Lime Stone (light Gray)	70	79	
Sand Stone (Gray)	79	105	
Sand Stone (light grey)	105	112	
" " (Dark grey)	112	163	
" " (grey)	163	250	
" " (green)	250	276	
" " (dark grey)	276	289	
" " (green)	289	306	
" " (light grey)	306	328	
" " (grey)	328	332	
Clay Stone (grey)	332	336	
Sand Stone (grey)	336	352	

Work started 10-10-83 Completed 10-15-83
Date well drilling machine moved off of well 10-15-83

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] George Robinson Date 10-17-1983

Bonded Water Well Constructor Certification:

Bond S261716 Issued by: Huggins
(number) Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name GEORGE ROBINSON DRILLING
(Person, firm or corporation) (Type or print)

Address 1050 Crescent Dr. N.W. Salem Ore.

[Signed] George Robinson
Water Well Constructor

Date 10-17-1983

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690