

WATER WELL REPORT
STATE OF OREGON

AUG 29 1983

WATER RESOURCES DEPT.
SALEM, OREGON
PLEASE TYPE or PRINT IN INK

State Well No. 85/2w-32
State Permit No.

(1) OWNER:

Name BEN WIPPER
Address 8062 Wipper Rd. S.E.
City Turner State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Battery Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
☒ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

6" Diam. from 6" ft. to 80" ft. Gauge 250
" Diam. from " ft. to " ft. Gauge

(6) LINER INSTALLED:

" Diam. from " ft. to " ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from " ft. to " ft.

Diam. Slot Size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

" " " "

Air test gal./min. with drill stem at ft. hrs.

Bailer test 48 gal./min. with 32 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Special standards: Yes ☒ No ☐

Well seal—Material used Cement, And Bentonite

Well sealed from land surface to 18" ft.

Diameter of well bore to bottom of seal 10" in.

Diameter of well bore below seal 6" in.

Number of sacks of cement used in well seal 2 Sacks Cement sacks

How was cement grout placed? 1 Sack Bentonite

Cement, And Bentonite Mixed, And Into

Seal Area.

Was pump installed? No Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL:

County Marion Driller's well number
Tax Lot # 1/4 Section 32 T. 8S R. 2W W.M.
Address at well location: 8062 Wipper Rd. S.E.
Turner, Oregon

(11) WATER LEVEL: Completed well.

Depth at which water was first found 18 ft.
Static level 5 ft. below land surface. Date 8-25-83
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 80 ft. Depth of completed well 80 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	1	
Clay, And Gravel	1	9	
Sand, And Gravel Medium To Large	9	14	
Cemented Gravel	14	22	
Sand, And Medium To Large Gravel	22	39	
Heaving Sand	39	43	
Medium To Large Gravel	43	54	
Heaving Sand	54	57	
Medium Gravels	57	63	
Medium To Large Gravels	63	75	
Large Gravels	75	80	5'
75' To 80' Water Bering			

Work started 8-17 19 83 Completed 8-26 19 83
Date well drilling machine moved off of well 8-26 19 83

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date 19

Bonded Water Well Constructor Certification:

Bond Issued by: Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name MILLER, WEST WELL DRILLING (Type or print)

Address 5875 Gaffin Rd S.E. Salem, Oregon

[Signed] Water Well Constructor

Date 8-26 1983

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690