

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the
STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

State Well No.

APR 12 1977

State Permit No.

(1) OWNER:

Name WILLIAM R. BABBITT
Address 2771 KUBLER RD. S
SALEM, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

6" Diam. from 0 ft. to 42' ft. Gage 1/4"
" Diam. from " ft. to " ft. Gage "
" Diam. from " ft. to " ft. Gage "

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from " ft. to " ft.
Diam. Slot size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? SNEED
Yield: 37.5 gal./min. with 103 ft. drawdown after 1 hrs.
" " " " " "
" " " " " "
Bailer test gal./min. with " ft. drawdown after " hrs.
Artesian flow g.p.m.

Temperature of water 53 Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Well seal—Material used BENTONITE
Well sealed from land surface to 42' ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal NONE sacks
Number of sacks of bentonite used in well seal 2 1/2 sacks
Brand name of bentonite WELL SEAL
Number of pounds of bentonite per 100 gallons
of water 100 lbs./100 gals.
Was a drive shoe used? ☐ Yes ☒ No Plugs NONE Size: location " ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: " ft.
Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL:

County MARION Driller's well number
1/4 SW 1/4 Section 8 T. 8S R. 3W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 251 ft.
Static level 229 ft. below land surface. Date 3-31-77
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 332 ft. Depth of completed well 332 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	2	
BASALT WEATHERED	2	35	
BASALT BROKEN	35	36	
BASALT DENSE	36	110	
BASALT BORDERS	110	112	
BAS. WLATH. GRAY HARD	112	120	
BASALT. POROUS	120	125	
BASALT DENSE	125	155	
BASALT FRACT.	155	167	
BASALT DENSE	167	247	
BASALT WLATH.	247	249	
BASALT FRACT	249	257	229
BAS. POROUS WITH W.B. IMBEDDED	257	268	
BASALT DENSE	268	316	
BAS. POROUS WITH W.B. IMBEDDED	316	318	
BASALT DENSE	318	320	
BASALT. POROUS WITH W.B. IMBEDDED	320	325	
BASALT DENSE	325	327	
BASALT FRACT	327	332	229

Work started 3-29 1977 Completed 3-31 1977

Date well drilling machine moved off of well 3-31 1977

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] James R. Sneed Date 4-10, 1977
(Drilling Machine Operator)

Drilling Machine Operator's License No. 940

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name J.A. SNEED & SONS (Type or print)
(Person, firm or corporation)

Address 4750 ELIZABETH AVE. SALEM, ORE.

[Signed] R. J. Sneed (Water Well Contractor)

Contractor's License No. 6 Date 4-10, 1977

(USE ADDITIONAL SHEETS IF NECESSARY)

SP*45658-119