

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

Do not write above this line

State Well No. 8s/3W-28

State Permit No. _____

(1) OWNER:

Name O H Duncan
Address 6355 Mustang Ct SE
Salem, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6 " Diam. from 1 ft. to 26 ft. Gage 350
4 " Diam. from 7 ft. to 41 ft. Gage PVC
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in.	by	in.
_____ perforations from _____ ft. to _____ ft.			
_____ perforations from _____ ft. to _____ ft.			
_____ perforations from _____ ft. to _____ ft.			

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type	Model No.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.	
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.	

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " " "

" Air " " " " "

Flow test 60 gal./min. with 144 ft. drawdown after 1 hrs.

Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to _____ 26 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 10 sacks

How was cement grout placed? Air grout Pump

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Marion Driller's well number _____
_____ 1/4 _____ 1/4 Section 28 T. 8S R. 3W W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 260 ft.

Static level 60 ft. below land surface. Date 10-25-79

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6 "

Depth drilled 804 ft. Depth of completed well 200 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	1	
Brown Clay	1	5	
Tan Clay	5	9	
Decomposed Rock with Tan Clay	9	14	
Boulder	14	19	
Decomposed Rock	19	23	
gray Basalt	23	30	
weathered Basalt	30	33	
gray Basalt	33	53	
weathered Basalt	53	55	
gray Basalt	55	61	
Black Basalt	61	66	
Claystone	66	78	
Black Basalt	78	107	
gray Basalt	107	149	
Black Basalt	149	204	

Work started 10-24 19 79 Completed 10-25 19 79

Date well drilling machine moved off of well 10-25 19 79

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Marc Mondell Date 10-26, 19 79
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1103

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Miller & West (Type or print)
(Person, firm or corporation)

Address 5875 Coffin Rd. SE

[Signed] Marc Mondell (Water Well Contractor)

Contractor's License No. 744 Date 10-26, 19 79