

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 85/3W-3166

State Permit No. _____

(1) OWNER:

Name Dennis Gilman
Address 5105 Commercial St SE
Salem, Oregon 97302

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6 " Diam. from 0 ft. to 340 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used torch
Size of perforations 1/8 in. by 6 in.
150 perforations from 230 ft. to 340 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" " " " " "
" " " " " "
Packer test air 45 gal./min. with 100 ft. drawdown after 1 hrs.
Artesian flow _____ g.p.m.
Temperature of water 53 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 9 in.
Number of sacks of cement used in well seal 7 sacks
How was cement grout placed? from bottom to top

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/4 pea
Gravel placed from 20 ft. to 340 ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 831079G
NW 1/4 NW 1/4 Section 31 T. 8S R. 34W W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 235 ft.
Static level 221 ft. below land surface. Date 10/30/79
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6 "

Depth drilled 350 ft. Depth of completed well 340 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
top soil	0	2	
reddish brown clay	2	29	
brown sandstone	29	75	
brown sandstone with	75	---	
streaks blue sandrock	---	148	
brown sandstone	148	189	
brown sandstone with	189	---	
streaks blue sandrock	---	262	
blue rock	262	270	
blue rock with streaks	270	---	
of brown sandstone	---	350	

RECEIVED RECEIVED
NOV - 11979 JAN 25 1980
WATER RESOURCES DEPT. WATER RESOURCES DEPT.
SALEM, OREGON SALEM, OREGON

Work started 10/25 1979 Completed 10/30 1979
Date well drilling machine moved off of well 10/30 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] George M. Harrison Date 10/31, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1072

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Schoen Electric & Pump
(Person, firm or corporation) (Type or print)

Address 626 W Queen, Albany, Ore 97321

[Signed] James E. Schoen
(Water Well Contractor)

Contractor's License No. 513 Date 10/31, 1979