

M. 21...

12962

WATER WELL REPORT
STATE OF OREGON

State Well No. 8/3w-33Q(2)

State Permit No.

(1) OWNER:

Name VALL, C. PRIEST
Address Route 3 Box 790
SALEM ORE.

(2) LOCATION OF WELL:

County Marion Owner's number, if any—
1/4 Section 33 T. 8 R. 3 W W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☒ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 86' ft. Gage 17"
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used TOREX
SIZE of perforations 7 in. by 6 in.
20" perforations from 40 ft. to 81 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Slot size Set from ft. to ft.
Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3'
Gravel placed from 40 ft. to 84' ft.
Was a surface seal provided? ☒ Yes ☐ No To what depth? 2' + ft.
Material used in seal— PUMP COVERED
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 8' ft. below land surface Date 6-5-61
Artesian pressure lbs. per square inch Date

Log Accepted by:

[Signed] Vallcrist Date June 6, 1961
(Owner)

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " "

Bailer test 40 gal./min. with 30 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water 56° Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 6" inches.
Depth drilled 86' 6" ft. Depth of completed well 86' 6" ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL	0	3
WEATHERED BASALT	3	21
MED CLAY STICKY	21	37
WEATHERED BASALT	37	66
CLAYSTONE FIRM.	66	84' 6"

CASING EQUIPPED WITH STEEL SHOE

1-6 P.M. @ 37'
11 P.M. @ 66'
28 P.M. @ 81'

Work started 6-3- 1961. Completed 6-5- 1961

(13) PUMP:

Manufacturer's Name
Type: H.P.

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME J. A. SNEED & SONS
(Person, firm, or corporation) (Type or print)

Address 2505 BROOKS ST. SALEM, ORE.

Driller's well number

[Signed] J. A. Sneed (Well Driller)

License No. 6 Date 6-5- 1961