

(Please type or print)

(Do not write above this line)

State Well No. 091E-9 CA

State Permit No. _____

Name Bud WALKER
Address 41025 M^c Cully Mtn Rd.
49005 OR. 97358

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

Rotary ☐ Driven ☐
 Jetted ☒
 Bored ☐

Domestic ☒ Industrial ☐ Municipal ☐
 Irrigation ☐ Test Well ☐ Other ☐

" Diam. from 11.5 ft. to 44 ft. Gage 1025
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

Type of perforator used TORCH

Size of perforations 3/16 in. by 8 in.

10 perforations from 35 ft. to 40 ft.

perforations from ft. to ft.

perforations from ft. to ft.

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield:	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"

Bailer test 9-10 gal./min. with 45 ft. drawdown after 1 hrs.

Artesian flow _____ g.p.m.

Temperature of water Depth artesian flow encountered ft.

Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 11 sacks

How was cement grout placed? _____

How was cement grout placed: Gravity flow

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☒ Yes ☐ No

Type of water? SURFACE depth of strata 12 ft.

Method of sealing strata off *Casing - Cement*

as well gravel packed? ☐ Yes ☒ No Size of gravel:

Level placed from ft. to ft.

County Marion Driller's well number _____
~~SE~~ $\frac{1}{4}$ 50 $\frac{1}{4}$ Section 9 T. 85 R. 1E W.M.

Bearing and distance from section or subdivision corner

Depth at which water was first found 12 ft

Static level ~~19~~ 19 ft. below land surface. Date 9-26-80

Artesian pressure lbs. per square inch. Date

Diameter of well below casing 6

Depth drilled 86 ft. Depth of completed well 86 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Small Bldes, gravel & Sand	0	15	12
Cobbles gravel Sand	15	22	
Boulders	22	28	
Conglomerate Course	28	44	
Conglomerate fine			
Volcanic Pink	44	49	
SHALE gray	49	70	19
SHALE gray/wh lenses			
fine gravel	70	86	19
RECEIVED OCT 29 1980 WATER RESOURCES DEPT SALEM, OREGON			

RECEIVED

OCT 29 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 9-15-1980 Completed 9-26 1980

Date well drilling machine moved off of well 9-26 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] L. E. Richardson Date 9-26, 1950
(Drilling Machine Operator)

Drilling Machine Operator's License No. 738

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name RICHARDSON Well Drilling
(Person, firm or corporation) (Type or print)

Address 5382 Sunnyview Rd Ne Salem

[Signed] Gene L. Richardson
(Water Well Contractor)

Contractor's License No. 650 Date 9-26- 1950