

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report  
are to be filed with the

WATER RESOURCES DEPARTMENT.  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

WATER WELL REPORT

STATE OF OREGON  
(Please type or print)

(Do not write above this line)

RECEIVED

JUL 13 1983

WATER RESOURCES DEPT.  
SALEM, OREGON

State Well No. 95/2W-6AC

Permit No. abandoned

(1) OWNER:

Name Charles Fowler Jr.  
Address 4255 Cloverdale Road, S.E.  
Salem, OR 97392

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☒

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

(4) PROPOSED USE (check):

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Dug ☐ Bored ☐  
Domestic ☒ Industrial ☐ Municipal ☐  
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

5/8" Diam. from +1 ft. to 33.9 ft. Gage -250  
NOTE: CASING REMOVED DURING ABANDONMENT  
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☐ No.

Type of perforator used

| Size of perforations | in. by | in. |
|----------------------|--------|-----|
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |

(7) SCREENS:

Well screen installed? ☐ Yes ☐ No

Manufacturer's Name  
Type Model No.  
Diam. Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller  
Yield: 33.6 gal./min. with ft. drawdown after 5 hrs.  
" " " "  
" " " "  
Bailer test 35 gal./min. with 25 ft. drawdown after 1 hrs.  
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

WELL ABANDONED.

Well seal—Material used Filled hole with concrete  
Well sealed from land surface to from 77' to surface.  
Diameter of well bore to bottom of seal in.  
Diameter of well bore below seal in.  
Number of sacks of cement used in well seal sacks  
How was cement grout placed? Hole was bailed dry and  
cement was poured into dry hole from  
a ready-mix truck.

Was a drive shoe used? ☐ Yes ☐ No Plugs Size: location ft.  
Did any strata contain unusable water? ☐ Yes ☐ No  
Type of water? depth of strata  
Method of sealing strata off  
Was well gravel packed? ☐ Yes ☐ No Size of gravel:  
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 605-169  
SW 1/4 NE 1/4 Section 6 T. 9 S. R. 2 W/ W.M.

Bearing and distance from section or subdivision corner  
Sunnyside Fruit Farm #5, FR Lot 1 & 2

(11) WATER LEVEL: Completed well.

Depth at which water was first found 37.6 ft.  
Static level 10.1 ft. below land surface. Date 7/5/83  
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

CASING REMOVED DURING

Diameter of well below casing ABANDONMENT.

Depth drilled ft. Depth of completed well ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL                                | From | To | SWL  |
|-----------------------------------------|------|----|------|
| Soil --Sandy Loam                       | 0    | 3  |      |
| Clay -- Light Brown                     | 3    | 15 |      |
| Boulders and Clay                       | 15   | 16 |      |
| Clay - Brown - Firm                     | 16   | 29 |      |
| Rock - Hard - Brown                     | 29   | 35 | 11.3 |
| Rock - Hard - Blue Basalt               | 35   | 53 | 10.1 |
| Rock - Basalt - Softer                  | 53   | 60 | "    |
| Rock - Basalt - Hard                    | 60   | 65 | "    |
| Rock - Basalt - Fractured               | 65   | 68 | "    |
| Rock - Basalt - Fractured and Weathered | 68   | 77 | "    |

NOTE: Cement surface seal leaked around casing into well and sealed formation off to approximately 5 gpm. Attempts to re-develop well were unsuccessful. Casing was pulled and hole was abandoned.

Work started Oct. 9 1981 Completed July 6 1983  
Date well drilling machine moved off of well July 6 1983

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John X. Hoeck Date July 6, 1983  
(Drilling Machine Operator)

Drilling Machine Operator's License No. WWC No. 605

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name HOECK WELL DRILLING  
(Person, firm or corporation) (Type or print)  
P. O. Box 1577, Eugene, OR 97477

Address  
[Signed] John X. Hoeck  
(Water Well Contractor)

Contractor's License No. 605 Date July 6, 1983