

RECEIVED

MAR 21.....

14621
MAR 1

95/2W-7a

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

NOV 21 1986

PLEASE TYPE or PRINT IN INK
WATER RESOURCES DEPT.

(for official use only)

(1) OWNER:

Name Jack Metcalfe (resident Rick Goff)
Address P.O. Box #36
City Turner 97392 State Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐
Cable ☐ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from 1 ft. to 127 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☐
" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? owner
d: 24 gal./min. with 60 ft. drawdown after 1 hrs.
Air test 25 gal./min. with drill stem at 260 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used cement grout
Well sealed from land surface to 125 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Amount of sealing material 38 sacks ☐ pounds ☐
How was cement grout placed? through 1 1/2" tremie grout pipe. Pumped with air diaphragm pump.
Was pump installed? owner Type sub HP 1 1/2 Depth 210 ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL by legal description:

County Marion NE 1/4 NE 1/4 of Section 7 of
Township 9S Range 2W WM.
(Township is North or South) (Range is East or West)

Tax Lot Lot Block Subdivision
MAILING ADDRESS OF WELL (or nearest address) 10100 Parrish Gap Road, Turner, Ore. 97392

(11) WATER LEVEL OF COMPLETED WELL:

Depth at which water was first found 230 ft.
Static level 39 ft. below land surface. Date 11/18/86
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"
Depth drilled 260 ft. Depth of completed well 260 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0'	5'	
Claystone (brown)	5'	10'	
Sandstone (green)	10'	25'	
Claystone (red brick)	25'	30'	
Basalt (brown weathered soft)	30'	38'	
Basalt (harder trend black brn)	38'	45'	
Basalt (black broke)	45'	80'	
Basalt (black seams)	80'	98'	
Basalt (brown yellow vesec.)	98'	105'	
Basalt (black & brown checked)	105'	120'	
Basalt (bright black)	120'	135'	
Basalt (gray black)	135'	150'	
Basalt (black hard)	150'	220'	
Basalt (brown black) (checked)	220'	230'	
Basalt (brown black vesec.)	230'	240'	39'
Basalt (bright black)	240'	260'	39'

Date work started 11/6/86 /completed 11/18/86
Date well drilling machine moved off of well 11/18/86 19

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Peter J. Tolmasoff Date 11/19, 19 86

(bonded) Water Well Constructor Certification:

Bond 2035392 Issued by: Western Surety Co.
(number) (Surety Company Name)
On behalf of Peter J. Tolmasoff
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Peter J. Tolmasoff
(Water Well Constructor)

(Dated) 11/19/86