

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

JUL 22 1975

WATER RESOURCES DEPT.

SALEM, OREGON

State Well No. 952w-17

State Permit No.

(1) OWNER:

Name **Mr. & Mrs. Joe Harter**Address **11045 Parrish Gap Rd. S.E., Turner**

(2) TYPE OF WORK (check):

New Well ☐ Deepening ☒ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 21 ft. Gage 250

" Diam. from EXISTING CASING Gage

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Appear to be none

Size of perforations 3/8 in. by 4 in. casing

Liner only perforated

20 perforations from 230 ft. to 210 ft.

20 perforations from 30 ft. to 210 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

Air lift 50" gpm from 230' after 1 1/2"

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used **Cement & aggreg.**Well sealed from land surface to **(side drilled) 18** ft.

Diameter of well bore to bottom of seal 6 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 2 sacks

Number of sacks of bentonite used in well seal --- sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons --- lbs./100 gals.

of water --- lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County **Marion**Driller's well number **794****NW 1/4 NW 1/4 Section 17 T. 9S R. 2W W.M.**

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found **140** ft.Static level **33** ft. below land surface. Date **7/9/75**

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing **6"**Depth drilled **231** ft. Depth of completed well **231** ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Existing well (60')	0'	120'	
Basalt (hard grey black)	120'	130'	
Basalt (hard-broken)	130'	137'	
Basalt (hard grey black)	137'	187'	
Basalt (brown & blue)	187'	199'	
Basalt (grey & black)	199'	205'	
Basalt (green & grey)	205'	231'	33'

Side drilled existing casing & grouted
with cement.

Installed 200' 5" O.D. well liner
perforated and set on well bottom.

Work started **7/7/75** 19 Completed **7/9/75** 19Date well drilling machine moved off of well **7/9/75** 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] **P. J. Tolmasoff** Date **7/10**, 19**75**(Drilling Machine Operator) License No. **320**

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name **Pete Tolmasoff Well Drilling**

(Person, firm or corporation) (Type or print)

Address **Turner, Ore.**[Signed] **Pete J. Tolmasoff**

(Water Well Contractor)

Contractor's License No. **410** Date **7/10/75**, 19**75**