

MARI 1448

MARI 1448
MARI..... Well Record

STATE ENGINEER
Salem, Oregon

STATE WELL NO. 4/3W-36J
COUNTY Marion
APPLICATION NO. GR-2702

OWNER: J. W. Richardson MAILING ADDRESS: Star Route, Box 17

LOCATION OF WELL: Owner's No. CITY AND STATE: St. Paul, Oregon

NE 1/4 SE 1/4 Sec. 36 T. 4 N. S, R. 3 W., W.M.

Bearing and distance from section or subdivision corner N. 16° 00' W. 2610'

Section

Altitude at well

TYPE OF WELL: Drilled Date Constructed 1951

Depth drilled 181' Depth cased 158'

CASING RECORD:

12 inch

FINISH:

4 holes mill knife from 80 ft. to 82 ft.
8 holes mill knife from 121 ft. to 123 ft.

AQUIFERS:

soil, clay, sand, gravel, shale and water

WATER LEVEL:

31 feet

PUMPING EQUIPMENT: Type Peerless Turbine H.P. 30
Capacity 650 G.P.M.

WELL TESTS:

Drawdown 100 ft. after hours pumping 400 G.P.M.
Drawdown 135 ft. after hours pumping 600 G.P.M.

USE OF WATER irrigation Temp. °F. 19

SOURCE OF INFORMATION GR-2560

DRILLER or DIGGER

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

MARI 1448

STATE ENGINEER
Salem, Oregon

State Well No. 4/3W-36J1
County Marion
Application No. _____

Well Log

Owner: J. W. Richardson Owner's No. _____

Driller: _____ Date Drilled _____

CHARACTER OF MATERIAL	(Feet below land surface)		Thickness (feet)
	From	To	
Surface soil	0	3	3
Clay	3	22	19
Clay, sandy	22	25	3
Clay, gray	25	30	5
Clay, gray, sandy	30	33	3
Clay, blue, sandy, yields some water	33	43	10
Clay, blue	43	58	15
Sand, black, muddy	58	73	15
Clay, blue	73	81	8
Sand and gravel, red	81	100	19
Clay, blue	100	122	22
Sand, black, water-bearing	122	124	2
Clay, brown	124	130	6
Sand, gray	130	134	4
Clay, brown	134	135	1
Sand, gray	135	140	5
Clay, green	140	148	8
Clay, blue	148	158	10
Sand and clay, broken	158	164	6
Shale and sand, hard	164	172	8
Sand, black, coarse, water-bearing	172	181	9
Casing: 12-inch to 158 feet; perforated, 80 to 82 feet, 121 to 123 feet.			



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for
Well ID Number

RECEIVED

MAR 09 2021

Do not complete if the well already has a Well Identification Number.

OWRD

I. OWNER INFORMATION

Current Owner Name (please print): RAY RICHARDSON

Mailing Address: 17901 RIVER RD NE

City, State, Zip: SAINT PAUL OR 97137

Mail Well ID to: [X] SAME AS ABOVE [] In Care Of (C/O)

Name & Address:

City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 4 S (North / South) Range: 3 W (East / West) Section: 36 NE 1/4 of the SE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 300 County MARION

GPS Coordinates: 45.1796350485 -122.9940318516 per WR map tool

Street Address of Well, City: 18111 RIVER RD NE

If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): IRRIGATION

Date Well Constructed (or property built): 1951 Total Well Depth: 181' Casing Diameter: 12"

Owner at time the well was constructed (if known): J W RICHARDSON Well Report # (if known): MARI 1448

Other Information: Groundwater registration GR 2702

SUBMITTED BY (please print): RAY RICHARDSON (VIA PHONE)

PHONE: 503-633-4691

EMAIL &/or FAX:

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301, fax to (503) 986-0902, or you are welcome to email the completed form to Ladeena.K.Ashley@oregon.gov.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

3-9-21

Well Report Number:

MARI 1448

Well Identification #:

L-141739