

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

NOV - 2 1977

MARI.....
14525
MARI

State Well No. 9S/2W-28

State Permit No.

(1) OWNER:

Name JAMES WOEHLER OREGON
Address 3290 LIBERTY RD SE
SALEM ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

6" Diam. from 0 ft. to 20 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations	in.	by	in.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" 100" of air " "

Bailer test 8 gal./min. with ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 9 in.

Diameter of well bore below seal in.

Number of sacks of cement used in well seal 14 sacks

How was cement grout placed? mixed up cement put in hole run bit up & down then push casing thru the cement

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County MARION Driller's well number

1/4 1/4 Section 28 T9S R.1W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 110 ft.

Static level 92 ft. below land surface. Date Oct 11/77

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 296 ft. Depth of completed well 296 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
BROWN CLAY	0	8	
BROWN STONE	8	13	
BLACK BASALT	13	32	
BROWN LAVA ROCK	32	35	
BLACK BASALT	35	37	
BROWN LAVA ROCK	37	41	
BLACK BASALT	41	110	
BROWN LAVA ROCK	110	119	
BLACK BASALT	119	136	
BROWN LAVA ROCK	136	133	
BLACK BASALT	133	296	
WATER BEARING			

Work started Oct 11 1977 Completed Oct 16 1977

Date well drilling machine moved off of well Oct 16 1977

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Melvin Search Date Oct 24, 1977
(Drilling Machine Operator)

Drilling Machine Operator's License No. 699

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name MELVIN SEARCHWELLDRIILLING
(Person, firm or corporation) (Type or print)

Address P.O. BOX 433 LEBANON ORE

[Signed] Melvin Search
(Water Well Contractor)

Contractor's License No. 567 Date Oct 24, 1977