

WATER WELL REPORT
STATE OF OREGON

RECEIVED

JUN 28 1984

State Well No. 95/2W-33bc

State Permit No.

WATER RESOURCES DEPT
SALEM, OREGON

(1) OWNER:

Name Ed & Esther Gisler
Address 5674 Marion Mill Road
City Turner, 97392 State Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rivary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
(☐ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from 1 ft. to 128 ft. Gauge .250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

1: gal./min. with ft. drawdown after hrs.

Air test 35 gal./min. with drill stem at 280 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

esian flow g.p.m.

perature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 128 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 30 sacks

How was cement grout placed? method C

Was pump installed? NO Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 1186
SW $\frac{1}{4}$ NW $\frac{1}{4}$ Section 33 T. 9S R. 2W W.M.
Tax Lot # Lot Blk Subdivision
Address at well location: Same

(11) WATER LEVEL: Completed well.

Depth at which water was first found 220 ft.
Static level 120 ft. below land surface. Date 5/29/84
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 280 ft. Depth of completed well 280 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0'	1'	
Clay (red brown)	1'	5'	
Claystone (red brown)	5'	22'	
Basalt & boulders (weathered)	22'	30'	
Basalt (orange brown weather)	30'	32'	
Basalt (broken weathered)	32'	60'	
Basalt (black sandy)	60'	110'	80'
Shale (grey & blue) (wood)	110'	120'	
Shale (tuffaceous dark)	120'	138'	
Shale (volcanics hard) (Dark)	138'	150'	
Shale (tuffaceous lavender)	150'	155'	
Shale (grey gritty tuff)	155'	250'	
Shale (volcanics dark)	250'	270'	
Shale (sandy marine fossils)	270'	280'	120'

Work started 5/18/84 19 Completed 5/29/84 19
Date well drilling machine moved off of well 5/29/84 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Pete Tolmasoff Date 5/31, 1984
(Drilling Machine Operator)

Drilling Machine Operator's License No. 120

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Pete Tolmasoff Well Drilling
(Person, firm or corporation) (Type or print)

Address 7332 MacRobbins Lane SE, Turner 97392

[Signed] Pete Tolmasoff
(Water Well Contractor)

Contractor's License No. 120 Date 5/31/84 19