

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 95/3w-4/bd

State Permit No. _____

(1) OWNER:

Name Keith Miller
Address 9441 Liberty Rd SE
Salem, Ore 97302

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Cable ☐
Driven ☐ Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 225 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used torch
Size of perforations 1/8 in. by 6 in.
140 perforations from 142 ft. to 225 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
gal./min. with ft. drawdown after hrs.
" " " "
" " " "
air 14 gal./min. with 100 ft. drawdown after 1 hrs.
Artesian flow g.p.m.
Temperature of water 54 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 9 in.
Number of sacks of cement used in well seal 10 sacks
How was cement grout placed? from bottom to top

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel 3/8 pea
Gravel placed from 28 ft. to 225 ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 891179G
SE 1/4 NW 1/4 Section 4 T. 9S R. 3W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 145 ft.
Static level 126 ft. below land surface. Date 11/20/79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 227 ft. Depth of completed well 227 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
top soil	0	1	
red clay	1	32	
brown sticky clay	32	40	
brown sandy claystone (soft)	40	121	
brown sandstone	121	155	
brown sandstone with	155	--	
streaks of blue rock	--	221	126'
fractured blue rock	221	227	

RECEIVED

NOV 28 1979

WATER RESOURCES DEPT
SALEM, OREGON

Work started 11/ 15 1979 Completed 11/ 19 1979

Date well drilling machine moved off of well 11/ 20 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Robert M. Simpson Date 11/26, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1072

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Schoen Electric & Pump
(Person, firm or corporation) (Type or print)

Address 626 W Queen Albany, Ore 97321

[Signed] George Schoen
(Water Well Contractor)

Contractor's License No. 513 Date 11/27, 1979