

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED WATER WELL REPORT

AUG 16 1977

(Please type or print)

(Do not write above this line)

Page "1" of 2

State Well No. 95/3W-31bd

State Permit No.

WATER RESOURCES DEPT.

(1) OWNER: SALEM, OREGON

Name Bruce Textroum

Address 1210 Rayvonne

Salem, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

(4) PROPOSED USE (check):

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐
Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 274 ft. Gage .250

5" Diam. from 268 ft. to 812 ft. Gage .250

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch

Size of perforations 3/16 in. by 6 in.

40 perforations from 330 ft. to 354 ft.

120 perforations from 402 ft. to 474 ft.

180 perforations from 546 ft. to 786 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Flow test 15 gal./min. with 490 ft. drawdown after 4 hrs.

Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Cement

Well seal—Material used

Well sealed from land surface to 25 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 8 sacks

How was cement grout placed?

hand mixed and hand placed

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 92877G

SE ¼ NW ¼ Section 31 T. 9S R. 3W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 324 ft.

Static level 260 ft. below land surface. Date 7/29/77

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 812 ft. Depth of completed well 812 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	2	
Redish Brow Clay	2	5	
Brown Sandy ?Claystone	5	16	
Redish Brown Clay	16	20	
Brown Sandy Claystone	20	24	
Fine Soft Brow Sandstone W/ streaks od med. Blue Sandstone	24	78	
Fine Brown Sandstone(fractured)			
W/streaks of Blue Rock	78	118	
Med. Blue Sandrock W/streaks of Blue Rock	118	132	
Blue Rock	132	136	
Brown Sandstone W/streaks of Blue Rock	136	188	
Blue Rock W/streaks of fine Brown Sandstone	188	292	260
Fine Black Rock	292	324	
Redish Brown/Green Sandy Clay	324	342	

Work started 7/29 19 77 Completed 8/9 19 77

Date well drilling machine moved off of well 8/9 19 77

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] George M. Simpson Date 8/13, 1977
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1072

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Water Boy's Well Drilling
(Person, firm or corporation) (Type or print)

Address 1416 East 32nd Albany, Oregon 97321

[Signed] Martin D. Hoffman
(Water Well Contractor)

Contractor's License No. 572 Date 8-15, 1977

SP*45656-119