

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 95/2E-10ba

State Permit No. _____

(1) OWNER:

Name Mike Wilber
Address 1901 Brandon Ave NE
Salem, Oregon 97303

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6" Diam. from 0 ft. to 38 ft. Gage 250
4" Diam. from 0 ft. to 150 ft. Gage pvc
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used saw cut
Size of perforations 1/8 in. by 6 in.
100 perforations from 50 ft. to 150 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
d: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" " " " " "
" " " " " "
Ball test air 20 gal./min. with 95 ft. drawdown after 1 hrs.
_____ esian flow _____ g.p.m.
Temperature of water 54 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 25 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 17 sacks
How was cement grout placed? from bottom to top

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 811079G
NE 1/4 NW 1/4 Section 10 T. 9S R. 2E W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 51 ft.
Static level 32 ft. below land surface. Date 10/22/79
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
large gravel, med. boulders	0	---	
& med. sand	---	8	
large gravel, med. boulders	8	---	
& brown clay	---	25	
brown sandy clay	25	28	
blue/gray sandy claystone	28	40	
brown sandy claystone	40	55	
gray claystone	55	118	32
med. gray sandstone	118	121	
med. gray sandstone (hard)	121	150	32

RECEIVED

OCT 30 1979

WATER RESOURCES DEPT
SALEM, OREGON

Work started 10/ 18 1979 Completed 10/ 22 1979
Date well drilling machine moved off of well 10/ 22 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] George M. Simpson Date 10/23, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1072

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Schoen Electric & Pump
(Person, firm or corporation) (Type or print)
Address 626 W Queen, Albany, Ore 97321

[Signed] George Schoen
(Water Well Contractor)

Contractor's License No. 513 Date 10/29, 1979