

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

RECEIVED
DEC 19 1967

WATER WELL REPORT

STATE OF OREGON

STATE ENGINEER, SALEM, OREGON 97310

ENGINEER (Please type or print)
within 30 days from the date
of well completion. SALEM, OREGON

(Do not write above this line)

State Well No. 10/3w-2

State Permit No.

(1) OWNER:

Name Small Tool Rental
Address 705 East 2nd Albany, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 47 ft. Gage 280
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch
Size of perforations 1/4 in. by 12 in.
10 perforations from 40 ft. to 45 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 13 ft. below land surface Date 7/1/67
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Id: gal./min. with ft. drawdown after hrs.
" " " " " "

Bailer test 50 gal./min. with 25 ft. drawdown after 30 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(10) CONSTRUCTION:

Well seal—Material used Beaumont
Depth of seal 18 ft.
Diameter of well bore to bottom of seal 9 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☐ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Marion Driller's well number
1/4 1/4 Section 2 T. 105 R. 3W W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing

Depth drilled 47 ft. Depth of completed well 47 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Large Boulders and Top Soil	0	14	
Medium Boulders, Co. Course Gravel and soil	14	21	
Large gravel and small Boulders	21	30	
Course Gravel and Sand	30	47	

Work started 6/28 1967 Completed 7/1/67 1967
Date well drilling machine moved off of well 7/1/67 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John Trach Date 7/1/67, 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 310

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME PALEY WELL DRILLERS (Type or print)
(Person, firm or corporation)

Address P.O. Box 885

SALEM, OREGON 97321
[Signed] Edmond Butts
(Water Well Contractor)

Contractor's License No. 253 Date 12-3, 1967