

#14

MAR 17269

6S/3W/24ab

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

(START CARD) # 25197

(1) OWNER: Well Number: 2918 Name BOLTMAN'S NURSERY INC. Address P.O. Box 9098 City Brooks, Oregon State 97305 Zip

(2) TYPE OF WORK: [X] New Well [ ] Deepen [ ] Recondition [ ] Abandon

(3) DRILL METHOD [X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Other

(4) PROPOSED USE: [ ] Domestic [ ] Community [ ] Industrial [X] Irrigation [ ] Thermal [ ] Injection [ ] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well 180' ft. Explosives used [ ] [X] Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Amount sacks or pounds. Row 1: 14, 0, 19, Dry Bentonite, 0, 19, 1350 pounds. Row 2: 8, 0, 180.

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E [ ] Other As Per 690-210-340 Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Diameter From To Gauge Steel Plastic Welded Threaded Casing: 8 +1 180 .250 [X] [ ] [X] [ ] Liner: Final location of shoe(s) 180'

(7) PERFORATIONS/SCREENS: [X] Perforations Method Mills Knife 5/16" X 2 3/4" [ ] Screens Type Material From To Slot size Number Diameter Tele/pipe size Casing Liner

(8) WELL TESTS: Minimum testing time is 1 hour [ ] Pump [ ] Bailer [X] Air [ ] Flowing Artesian Yield gal/min Drawdown Drill stem at Time

Temperature of water 53.0 Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Marion Latitude Longitude Township 6S N or S, Range 3W E or W, WM. Section 24 NW 1/4 NE 1/4 Tax Lot Lot Block Subdivision Street Address of Well (or nearest address) 8375 River Rd. N.E.

(10) STATIC WATER LEVEL: 37 ft. below land surface. Date 4/12/91 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 76 Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 76, 141, 1000+, 37. Row 2: 157, 180, 1000+, 37.

(12) WELL LOG: Ground elevation Table with columns: Material, From, To, SWL. Rows: Topsoil (0-2), Brown Clay (2-76), Black Sand (76-79), Muddy Black Sand and Gravel (79-94), Cemented Brown Sand and Gravel (94-106), Loose Brown Sand and Gravel (106-135), Reddish Brown Sand and Gravel (135-145), Blue Clay (145-157), Black Sand (157-175), Black Sand and Gravel (175-180). Includes RECEIVED stamp dated MAY 17 1991 and WATER RESOURCE DEPT. SALEM, OREGON.

Date started 4/11/91 Completed 4/12/91

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Signed Mark D. Beis WWC Number 753 Date 4/12/91

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. Signed Mark D. Beis WWC Number 753 Date 4/12/91



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Robert W. Gabriel Trust, Robert Gabriel Trustee -----See Well Log MARI 17269

Mailing Address: 8474 Hazelgreen Rd NE

City, State, Zip: Silverton, OR 97381

RECEIVED BY OWRD

Mail Well ID Tag to: [X] SAME AS ABOVE [ ] In Care Of (C/O)

MAR 13 2017

Name & Address:

City, State, Zip:

SALEM, OR

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 6S (North / South) Range: 3W (East / West) Section: 24 NW 1/4 of the NE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): TL 06 2W 24A(1900) County Marion

GPS Coordinates:

Street Address of Well, City: 8375 River Rd NE, Salem, OR 97303

If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation

Date Well Constructed (or property built): April 12, 1991 Total Well Depth: 180 feet Casing Diameter: 8 inch

Owner at time the well was constructed (if known): Boltman's Nursery Inc. Well Log # (if known): MARI 17269

Other Information:

SUBMITTED BY (please print): Robert Gabriel

PHONE: (503) 873-1200

EMAIL &/or FAX: (503) 873-1300

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

3-13-17

Well Log Number:

MARI 17269

Well Identification #:

L-125719