

14

AUG - 5 1991

MARI 17388

65/30/23 ad

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

WATER RESOURCES DEPT. SALEM, OREGON

(START CARD) # 30566

(1) OWNER: Well Number: 2935 Name RICK JOHNSON Address 1585 Clearlake Rd. N.E. City Keizer, Oregon 97303 State Zip

(2) TYPE OF WORK: [X] New Well [ ] Deepen [ ] Recondition [ ] Abandon

(3) DRILL METHOD [X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Other

(4) PROPOSED USE: [ ] Domestic [ ] Community [ ] Industrial [X] Irrigation [ ] Thermal [ ] Injection [ ] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well 200' ft. Explosives used [ ] [X] Type Amount

Table with columns: HOLE Diameter, SEAL Material, Amount sacks or pounds. Row 1: 14, 0, 19, 1200lbs., 0, 19, Dry Bentonite. Row 2: 8, 0, 200, , , ,

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E [ ] Other As Per 690-210-340 Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 8", +1, 200, .250, [X], [ ], [X], [ ]. Liner: [ ], [ ], [ ], [ ]. Final location of shoe(s) 200'

(7) PERFORATIONS/SCREENS: [X] Perforations Method Mills Knife (3/8" X 2 1/2") [ ] Screens Type Material. Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 120, 150, , 312, , , [X], [ ]. Row 2: 183, 200, , 240, , , [X], [ ].

(8) WELL TESTS: Minimum testing time is 1 hour [ ] Pump [ ] Bailer [X] Air [ ] Artesian. Yield gal/min 500+, Drawdown, Drill stem at 199, Time 1 hr.

Temperature of water 53° Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Marion Latitude Longitude Township 6S N or S, Range 3W E or W, WM. Section 23 SE 1/4 NE 1/4 Tax Lot Lot Block Subdivision Street Address of Well (or nearest address) 1585 Clearlake Rd. N.E.

(10) STATIC WATER LEVEL: 62 ft. below land surface. Date 6/19/91 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 75. Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 75, 200, XXXX1000+,

(12) WELL LOG: Ground elevation. Table with columns: Material, From, To, SWL. Topsoil 0-2, Brown Clay 2-62, Gray Clay 62-75, Cemented Black Sand and Gravel 75-91, Cemented Brown Sand and Gravel 91-150, Blue Clay 150-172, Cemented Black Sand and Gravel 172-180, Black Sand and Gravel 180-200.

Date started 6/17/91 Completed 6/19/91

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. Signed Mark D. Beier WWC Number 753 Date 6/20/91

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. WILLAMETTE DRILLING CO. Signed Mark D. Beier WWC Number 753 Date 6/20/91



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

RECEIVED BY OWRD

MAR 13 2017

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

SALEM, OR

Current Owner Name (please print): Clearlake Farms LLC c/o Robert Gabriel----- See Well log MARI 17388

Mailing Address: 8474 Hazelgreen Rd NE

City, State, Zip: Silverton, OR 97381

Mail Well ID Tag to: [X] SAME AS ABOVE [ ] In Care Of (C/O)

Name & Address:

City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 6 South (North / South) Range: 3 West (East / West) Section: 23 SE 1/4 of the NE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): TL 06 3W 23A(1100) County Marion

GPS Coordinates:

Street Address of Well, City: 1585 Clear Lake Rd NE, Keizer, OR 97303

If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Domestic, Irrigation

Date Well Constructed (or property built): 6-19-91 Total Well Depth: 200 feet Casing Diameter: 8 inch

Owner at time the well was constructed (if known): Rick Johnson Well Log # (if known): MARI 17388

Other Information:

SUBMITTED BY (please print): Robert Gabriel

PHONE: (503) 873-1200 EMAIL &/or FAX: (503) 873-1300

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

3-13-17

Well Log Number:

MARI 17388

Well Identification #:

L-125718