

STATE OF OREGON  
**WATER WELL REPORT**  
 (as required by ORS 537.765)

Mari  
17545

**RECEIVED**

NOV - 4 1991 (START CARD) # 43/1W-11  
28886

(1) OWNER: Well Number: \_\_\_\_\_  
 Name JEFF ALZNER  
 Address 8100 SW 71  
 City TIGARD State OREG. Zip \_\_\_\_\_

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  
 Other \_\_\_\_\_

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION:  
 Special Construction approval Yes  No  Depth of Completed Well 112 ft.  
 Explosives used Yes  No  Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
<u>12</u>	<u>0</u> <u>22</u>	<u>BENTONITE</u>	<u>0</u> <u>2</u>	<u>22 SACKS</u>	
<u>8</u>	<u>22</u> <u>132</u>				

How was seal placed: Method  A  B  C  D  E  
 Other POURED  
 Backfill placed from 112 ft. to 122 ft. Material GRAVEL  
 Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:  

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
<u>8"</u>	<u>+1</u>	<u>107</u>	<u>250"</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

  

Liner:	From	To	Steel	Plastic	Welded	Threaded
			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of sheets: \_\_\_\_\_

(7) PERFORATIONS/SCREENS:  
 Perforations Method PULL-BACK  
 Screens Type \_\_\_\_\_ Material STAINLESS

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
<u>107</u>	<u>112</u>	<u>40</u>		<u>7"</u>	<u>8"</u>	<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailer  Air  Flowing Artesian  

Yield gal/min	Drawdown	Drill stem at	Time
<u>20</u>	<u>20</u>		<u>1 hr.</u>

Temperature of water 56° Depth Artesian Flow Found \_\_\_\_\_  
 Was a water analysis done?  Yes By whom \_\_\_\_\_  
 Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
 Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
 County CLATSOP Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
 Township 43 N or S. Range 1W E or W. WM.  
 Section 11 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_  
 Tax Lot 40375-00 Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
 Street Address of Well (or nearest address) \_\_\_\_\_

(10) STATIC WATER LEVEL:  
61 ft. below land surface. Date 10/16/91  
 Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
 Depth at which water was first found \_\_\_\_\_

From	To	Estimated Flow Rate	SWL
<u>#3</u>	<u>122</u>		
<u>106</u>	<u>113</u>		<u>61</u>

(12) WELL LOG: Ground elevation \_\_\_\_\_

Material	From	To	SWL
<u>TOP SOIL</u>	<u>0</u>	<u>2</u>	
<u>SILTY BROWN CLAY</u>	<u>2</u>	<u>30</u>	
<u>FINE BROWN SAND</u>	<u>30</u>	<u>54</u>	
<u>SILTY BLUE CLAY</u>	<u>54</u>	<u>72</u>	
<u>BLUE CLAY</u>	<u>72</u>	<u>76</u>	
<u>BLUE SILTY CLAY</u>	<u>76</u>	<u>95</u>	
<u>BLACK SAND</u>	<u>95</u>	<u>96</u>	
<u>FINE BLACK SAND</u>	<u>96</u>	<u>106</u>	
<u>LOOSE GRAVEL</u>	<u>106</u>	<u>113</u>	
<u>CEMENTED GRAVEL</u>	<u>113</u>	<u>117</u>	<u>61</u>
<u>BLUE CLAY, STICKY</u>	<u>117</u>	<u>122</u>	

Date started 10/2/91 Completed 10/16/91

(unbonded) Water Well Constructor Certification:  
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
 Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
 Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
 Signed Cl Ken WWC Number \_\_\_\_\_  
 Date 10/31/91