STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MAR1 17895

RECEIVED JUN 11 1992 SALEM, OREGON

6S/1E/30ba

(START CARD) # 41579

(1) OWNER:
Well Number: WATER R

Name: Henry Kuzmin
Address: 14006 Monitor McKee Rd
City: Mt. Angel, State: Oregon Zip: 97362

(2) TYPE OF WORK:
[X] New Well [ ] Deepen [ ] Recondition [ ] Abandon

(3) DRILL METHOD
[X] Rotary Air [ ] Rotary Mud [ ] Cable
[ ] Other

(4) PROPOSED USE:
[ ] Domestic [ ] Community [ ] Industrial [X] Irrigation
[ ] Thermal [ ] Injection [ ] Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes [ ] No [X] Depth of Completed Well 138 ft.
Explosives used Yes [ ] No [X] Type Amount

HOLE Diameter	From	To	SEAL Material	From	To	Amount sacks or pounds
12"	0	120	Bentonite	0	25	30
8"	120	138				

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E
[ ] Other poured dry
Backfill placed from 25 ft. to 35 ft. Material bentonite
Gravel placed from 35 ft. to 120 ft. Size of gravel 3/4 round

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+2	138	.025	[X]	[ ]	[X]	[ ]
					[ ]	[ ]	[ ]	[ ]
					[ ]	[ ]	[ ]	[ ]
					[ ]	[ ]	[ ]	[ ]
Liner:					[ ]	[ ]	[ ]	[ ]
					[ ]	[ ]	[ ]	[ ]

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:
[X] Perforations Method air perf
[ ] Screens Type star Material steel

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
97	135	1/4x1	640	8"		[X]	[ ]
						[ ]	[ ]
						[ ]	[ ]
						[ ]	[ ]
						[ ]	[ ]
						[ ]	[ ]

(8) WELL TESTS: Minimum testing time is 1 hour
[ ] Pump [ ] Bailer [X] Air [ ] Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
250		120	1 hr.

Temperature of water 56 Depth Artesian Flow Found
Was a water analysis done? [ ] Yes By whom
Did any strata contain water not suitable for intended use? [ ] Too little
[ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County Marion Latitude ' " Longitude ' "
Township 6 S. N or S. Range 1 E. E or W, WM.
Section 30 NE ¼ NW ¼
Tax Lot 63728-001 Lot Block Subdivision
Street Address of Well (or nearest address) S. Abiqua Rd

(10) STATIC WATER LEVEL:
54 ft. below land surface. Date 5-6-92
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 51'

From	To	Estimated Flow Rate	SWL
94	138	250 gpm	

(12) WELL LOG:
Ground elevation

Material	From	To	SWL
top soil	0	1	
clay brown sticky	1	7	
boulders and cobbles	7	17	
sticky clay red withcobbles			
sticky clay red	22	51	
rock highly decomposed and			
weathered clay like	51	76	
basalt weathered & broken			
with gravel innerbeds	76	91	
basalt broken gravel brown	91	94	
basalt weathered highly			
broken porous	94	127	
basalt weathered highly broken	127	138	

Date started 4-30-92 Completed 5-7-92

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
WWC Number
Signed Date 6-9-92

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
WWC Number
Signed Date 6-9-92