

RECEIVED

MAR 23 1978

WATER RESOURCES DEPT.

Table 2.--Drillers' logs of representative wells. Continued

5/1W-18C4. City of Woodburn. Altitude 181 ft.

Materials	Thickness (feet)	Depth (feet)
Top soil and clay -----	6	6
Clay, sandy -----	39	45
Quicksand -----	25	70
Clay, sandy, with occasional gravelly streaks -----	45	115
Gravel, cemented -----	2	117
Sand, black, water-bearing -----	5	122
Gravel with "binder" -----	20	142
Clay, sticky -----	8	150
Sand and clay -----	15	165
Clay and gravel -----	3	168
Gravel and sand, water-bearing -----	8	176
Gravel, tight -----	8	184
Gravel, water-bearing -----	8	192
Wood and silt -----	6	198

Casing: 12-inch to 192+ ft; perforated from 172 to 177 ft and
from 178 to 192 ft.



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

Do not complete if the well already has a Well I.D Number.

I. OWNER INFORMATION

Current Owner Name (please print): City of Woodburn, OR.
Mailing Address: 270 Montgomery St
City: Woodburn State: OR. Zip: 97071
Mailing Address (to send Well I.D.): "Above"
City: State: Zip:

II. WELL INFORMATION (Do not complete this section if the well report is attached.)

Township: 55 (North/South) Range: 1W (East/West) Section: 18
Tax Lot: 1100 County: Marion NE 1/4 NW 1/4
Street Address of Well: 280 Garfield (Public Library) City: Woodburn
Owner at time the well was constructed, (if known):
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Do not complete this section if the well report is attached)

Use of Well (domestic, irrigation, commercial, industrial, monitoring):
Date Well Constructed: Total Well Depth: Casing Diameter:
Other Information: "well #3"

SUBMITTED BY (please print): Dennis R. Samson
PHONE: 503-982-5380 FAX: 982-7846

Send application to Oregon Water Resources Department; 725 Summer St NE, Suite A; Salem, Oregon 97301-1266; fax (503) 986-0902. Applications are processed and Well I.D. Numbers are mailed every Wednesday.

For Official Use Only by the Oregon Water Resources Department:
Received Date: 12-11-08
Well Log Number: MARI 1850 (orig)
Well Identification #: L-99852

MARI 1834 (alt)

RECEIVED

Last Update: 11/04/08

Well I.D. Number/ I

DEC 11 2008

WCC

* revised to add tax lot, QQ, address etc per Groundwater site est. 2001.

WATER RESOURCES DEPT
SALEM, OREGON