

RECEIVED

85/3w/14da
70626

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

16
Mare
19217

SEP 20 1994

WATER RESOURCES DEPT. (START CARD) #
SALEM, OREGON

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 2763
Name John Miller
Address 2537 Landau St. SE
City Salem State OR Zip 97306

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 325 ft.
Explosives used Yes No Type Amount

HOLE		SEAL		Sacks or pounds	
Diameter	From To	Material	From To		
10	0 50	Cement	0 50	20 sacks	
6	0 325	Bore			

How was seal placed: Method A B C D E
 Other

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	2	50	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: NONE				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) NONE

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Material	Tele/pipe size	Casing	Liner
NONE								

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min 25gpm Drawdown Drill stem at 300 Time 1 hr.

Temperature of water 56° Depth Artesian Flow Found
Was a water analysis done? Yes By whom
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County MARION Latitude Longitude
Township 8 N or S Range 3 E or W WM.
Section 14 NE 1/4 SE 1/4
Tax Lot Lot Block Subdivision
Street Address of Well (or nearest address) 2537 Landau St. SE Salem, OR 97306

(10) STATIC WATER LEVEL:
30 ft. below land surface. Date 9.19.94
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 65

From	To	Estimated Flow Rate	SWL
65	85	1	30
85	105	2	30
120	122	4	30
275	287	18	30

(12) WELL LOG:
Ground Elevation

Material	From	To	SWL
Topsoil	0	1	
Brown Clay Cemented Bhrs	1	25	
Cemented Boulders	25	45	
Basalt	45	165	
Black Claystone	165	170	
Brown Claystone	170	175	
Basalt	175	200	
Brown Basalt & Pumico	200	205	
Basalt	205	315	30
Blue Sandstone	315	325	

Date started 9-15-94 Completed 9-19-94

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed [Signature] WWC Number 1179 Date

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed [Signature] WWC Number 514 Date 9/29/94