

STATE OF OREGON
WATER-WELL REPORT
(as required by ORS 537.765)

(START CARD) # 70040

(1) OWNER:

Name Chuck & Sheila Goode Well Number 3
Address 18103 Powers Crk Loop Rd
City Silverton State Ore Zip 97381

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 320 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
6"	79 320	cement	22 74	20 sak	
10"	0 74	Bentonite	0 22	12 sak	

How was seal placed: Method ☐ A ☐ B ☐ C ☒ D ☐ E
☒ Other Filled to top with Dry Bentonite

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+1	79'	250	☒	☐	☒	☐
Liner:	4"	5	320	160	☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method saw cut
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
220	320	1/8	60	6" long		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
8 GPM			1 hr.

Temperature of Water 54° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Marion Latitude _____ Longitude _____
Township 8 S N or S. Range 4 W E or W. WM.
Section 23 SW 1/4 NE 1/4
Tax Lot 220#3 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 5540 Vitae Springs Rd Salem Ore

(10) STATIC WATER LEVEL:

_____ ft. below land surface. Date 2/9/95

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
100	320	8 GPM	

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
Soil	0	2	
Brown clay	2	17	
orange/ partly weatherd	17	27	
Tan Weatherd - Rock	27	43	
Rock	43	51	
partly weatherd Rock	51	68	
gray claystone	68	107	
gray clay	107	114	
clay stone w/ Hard	114		
layers		320	
RECEIVED			
MAR 02 1995			
WATER RESOURCES DEPT			
SALEM, OREGON			
ROBINSON DRILLING			
WELLS & PUMPS			
4520 Dallas-Salem Hwy.			
Salem, Ore. 97304			
371-1844			

Date started 1/30/95 Completed 2/9/95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1585 Date 2-10-95