

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

MAR 02 1995

WATER RESOURCES DEP.

(START CARD)

70064

(1) OWNER:

Name Gerald E. Hastings
Address 5776 Barcelona DR SE Salem
City Salem State Ore Zip 97301

Well Number 4 1 SALEM,

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 303 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	39'	cement	0	39	12 sak.
6"	39'	303'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	1	39	250	☒	☐	☒	☐
Liner:	4"	1	303	160	☐	☒	☒	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method sawcut
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
223	303	1/8	64	6" long		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Artesian

Yield gal/min	Drawdown	Drill stem at	Time
50 GPM		303	1 hr.

Temperature of Water 53° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Marion Latitude _____ Longitude _____
Township 7 S N or S. Range 2 W E or W. WM. _____
Section 36 SW 1/4 ne 1/4
Tax Lot 05800 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 8731 Boulder Ridge
Salem Ore SE

(10) STATIC WATER LEVEL:

128' ft. below land surface. Date 2/23/95

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
282'	303'	50 GPM	

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
soil	0	2	
Boulders large	2	18	
Rock	18	24	
Brown weathered Rock	24	26	
Rock Honey Cone w/Red	26	29	
carbon shale	29	32	
Rock	32	90	
Rock w/white seems	90	103	
Rock Black	103	113	
Rock Brown	113	119	
Rock	119	128	
Rock w/ gray hard layer	128		
		303	

ROBINSON DRILLING
WELLS & PUMPS
4520 Dallas-Salem Hwy.
Salem, Ore. 97304
371-1844

Date started 2/17/95 Completed 2/23/95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 13
Signed Darryl Robinson Date 2-23-95