

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

RECEIVED

JUL 12 1995

(START CARD) # 75241

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number SALE
Name Larry Epping Bldg. Co.
Address 2485 Lancaster Dr. NE
City Salem State OR Zip 97305

(2) TYPE OF WORK
☐ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☒ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation prior use
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION: orig.
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 117 ft.
Explosives used ☐ Yes ☐ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
8" orig.						

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	approx	Gauge	Steel	Plastic	Welded	Threaded
orig. 8"	1' +	117'	.250	☒	☐	☒	☐
Casing:				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner:				☐	☐	☐	☐
				☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
☒ Perforations Method Mills knife
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
1'	105'	2x3"	approx 400	8"		☒	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump	☐ Bailer	☐ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stem at	Artesian
N.A.			1 hr.

Temperature of water _____ Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Marion Latitude _____ Longitude _____
Township 7 S N or S Range 2 W E or W. WM. _____
Section 6 SW 1/4 NE 1/4
Tax Lot 189 acc. 82615-88 Plan Ree Meadows division
Street Address of Well (or nearest address) 4336 Raccoon DR NE
Salem, OR 97305

(10) STATIC WATER LEVEL:
was 46 ft. below land surface. Date 6-20-95
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found N.A.

From	To	Estimated Flow Rate	SWL

(12) WELL LOG:
Ground Elevation approx 180'

Material	From	To	SWL
We abandoned this irrigation well by perforating the 8" casing from 1 ft. to 105 ft. & filling back with 1/4" minus rock from 117' up to approx. 95' & pumped in 45 sacks of grout & let it set over night & it only raised up 9 ft. So we put in approx. 15 ft. more of 6" crushed rock & then pumped in 50 more sacks of cement grout.			
95 sacks total of cement & 1/2 sack of hole plug on top to bring it approx 1 1/2' from surface.			

Date started 6-14-95 Completed 6-24-95

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Maurice A. Stadel WWC Number 1363 Date 7-8-95

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Paul R. Stadel WWC Number 296 Date 7-10-95