

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

SEP 7 - 1995

095/020/27 AC

(START CARD) # 82366

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Name Melix & Sarah Nolan

Address 1142 Wiltsey Rd SE

City Salem State Ore Zip 97306

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 320 ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	40	cement	40	79	4 bags
3"	40	79	bentonite	0	40	22 bags
6"	79	320				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☒ Other filled to top with dry bentonite

Backfill placed from 320 ft. to 335 ft. Material 1/2-crush
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	79	250	☒	☐	☒	☐
Liner: 4"	0	320	160	☒	☐	☒	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations Method SAW cut

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
260	320	1/8	40	6" long		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing ☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
15 gpm		320	1 hr.

Temperature of water 54° Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Marion Latitude Longitude

Township 9 S N or S Range 2 W E or W. WM.

Section 27 SW 1/4 ne 1/4

Tax Lot 62055 Lot Block Subdivision

Street Address of Well (or nearest address)

15241 Woodland Ln SE

(10) STATIC WATER LEVEL:

251' ft. below land surface. Date 9/5/95

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found

From	To	Estimated Flow Rate	SWL
260	320	15 gpm	

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
gravel	0	1	
Brown clay w/rock	1	18	
Brown clay / Broken Rock	18	65	
Rock Hard	65	85	
Rock w/gray layers	85	215	
Rock black hard	215	303	
Rock Broken	303	311	
Rock w/ Brown stains	311	320	

ROBINSON DRILLING
WELLS & PUMPS
4520 Dallas-Salem Hwy.
Salem, Ore. 97304
371-1844

Date started 8/22/95 Completed 9/5/95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1585

Signed Date 9-7-95