

STATE OF OREGON  
**WATER WELL REPORT**  
 (as required by ORS 537.765)

RECEIVED

MARI 2006

JUL 19 1988

55/1W-27ba  
 Start card # 3022

(1) **OWNER:**  
 Name Woodburn Ornamentals  
 Address 13009 Mckee School Rd.  
 City Woodburn State OR Zip 97071

(2) **TYPE OF WORK:**  
 New Well  Deepen  Recondition  Abandon

(3) **DRILL METHOD**  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) **PROPOSED USE:**  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) **BORE HOLE CONSTRUCTION:**  
 Special Construction approval Yes  No  Depth of Completed Well 118 ft.  
 Explosives used  Yes  No  Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
12	0 18	Bent.	0 20	10 sacks	
8	18 118	-----	---	-----	

How was seal placed: Method  A  B  C  D  E  
 Other dry sacks Poured in #8  
 Backfill placed from \_\_\_ ft. to \_\_\_ ft. Material \_\_\_\_\_  
 Gravel placed from \_\_\_ ft. to \_\_\_ ft. Size of gravel \_\_\_\_\_

(6) **CASING/LINER:**

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	+1 1/2	118	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 118

(7) **PERFORATIONS/SCREENS:**

Perforations Method Air perforator  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
95	115	1/2"	720	8"	P	<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) **WELL TESTS: Minimum testing time is 1 hour**

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
approx. 300		118	1 hr.

Temperature of water \_\_\_\_\_ Depth Artesian Flow Found \_\_\_\_\_  
 Was a water analysis done?  Yes By whom \_\_\_\_\_  
 Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
 Depth of strata: \_\_\_\_\_

(9) **LOCATION OF WELL by legal description:**  
 County Marion Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
 Township 5S N or S, Range 1W E or W, WM.  
 Section 27 NE 1/4 NW 1/4  
 Tax Lot \_\_\_\_\_ Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
 Street Address of Well (or nearest address) 13188 McKee School Rd Woodburn, OR 97071

(10) **STATIC WATER LEVEL:**  
 \_\_\_\_\_ ft. below land surface. Date 7-14-88  
 Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) **WATER BEARING ZONES:**

Depth at which water was first found 57'

From	To	Estimated Flow Rate	SWL
57	62	50 gpm	
93	118	300 gpm	

(12) **WELL LOG:** Ground elevation \_\_\_\_\_

Material	From	To	SWL
Top soil	0	4	
Brown clay	4	22	
Grey clay sticky	22	46	
Sand brown fine	46	57	
Sand & gravel med	57	62	WB
Gravel coarse	62	82	
Sandstone	82	93	
Gravel coarse	93	118	WB
Clay grey	118	---	

Date started 7-12-88 Completed 7-14-88

(unbonded) **Water Well Constructor Certification:**  
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
 Signed Jon McElwain WWC Number \_\_\_\_\_ Date \_\_\_\_\_

(bonded) **Water Well Constructor Certification:**  
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
 Signed [Signature] WWC Number 723 Date 7-15-88

RECEIVED

MARI 2006

№ 3022

JUL 15 1988

"START CARD"

WATER RESOURCES DEPT.  
SALEM, OREGON

NOTICE OF BEGINNING OF WELL CONSTRUCTION  
(as required by ORS 537.762)

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and Mailing Address Woodburn Ornamentals, Inc.  
13009 McKee School Rd.  
Woodburn, OR 97071

Proposed Commencement Date 7-13-88

Proposed Well Depth 130-140, Diameter 8"  
and Use:  
 Domestic       Community       Industrial       Irrigation  
 Thermal       Injection       Other

Proposed Well Location: County Marion  
Township 5S (N or S) Range 1W (E or W) Section 27

At least 2 of these must be provided

1. NE 1/4 of NW 1/4 of above section
2. street address of well location 13188 McKee School Rd.  
Woodburn, OR 97071
3. tax lot number of well location \_\_\_\_\_
4. attach approved map with location identified.  
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

x Tom Fisher  
Owner's Signature

x [Signature]  
Bonded Water Well Constructor

UP  
Title

License No. 723

7-13-88  
Date

Company Staco Well Services

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.