

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

RECEIVED WATER WELL REPORT

FEB 19 1975

STATE OF OREGON

JUN 1974

State Well No.

4S/1W-2a

STATE ENGINEER, SALEM, OREGON 97301

within 30 days from the date
of well completion.

STATE ENGINEER
SALEM, OREGON

(Please type or print)

STATE ENGINEER State Permit No.

SALEM, OREGON

(1) OWNER:

Name William R. Hoehnke Nursery
Address Rt. 3 Box 704
Aurora, Oregon 97002

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

10" Diam. from 0 ft. to 138 ft. Gage 335
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills Knife

Size of perforations 1/4 in. by 2 in.
60 perforations from 133 ft. to 137 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Air
Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller

Yield: 200 gal./min. with 66 ft. drawdown after 6 hrs.

" " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 30 ft.
Diameter of well bore to bottom of seal 15 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 0 sacks
Number of sacks of bentonite used in well seal 8 sacks
Brand name of bentonite Bariod Mud Gel
Number of pounds of bentonite per 100 gallons
of water 100 lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 33-74
1/4 NE 1/4 Section 2 T. 4S R. 1W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 15 ft.

Static level 59 ft. below land surface. Date 5-29-74

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10

Depth drilled 141 ft. Depth of completed well 138 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	3	
Brown clay	3	12	
Brown sandy clay	12	24	
Brown clay	24	30	
Cousre sand	30	33	
Blue sandy clay	33	75	
Fine grey sand	75	85	
Grey clay	85	102	
Green clay	102	120	
Fine Grey sand	120	126	
Gravel & sand	126	140	59
Green clay	140	141	

Work started 5-21- 19 74 Completed 5-28 19 74

Date well drilling machine moved off of well 5-28 19 74

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Date 6-3, 19 74
(Drilling Machine Operator)

Drilling Machine Operator's License No. 271

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Skyles Drilling and Supply
(Person, firm or corporation) (Type or print)

Address 1169 Molalla Avenue, Oregon City

[Signed] Marvin A. Skyles
(Water Well Contractor)

Contractor's License No. 553 Date 6-3, 19 74