

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
WATER WELL REPORT
STATE OF OREGON
AUG 17 1978

(Please print name or print)

WATER RESOURCES DEPT.
SALEM, OREGON

State Well No. 6524-1999

State Permit No.

(1) OWNER:

Name Raymond Zollner
Address 9134 McAngel-Gervais Rd
Gervais Ore 97017

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 145 ft. Gage 0250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used STAR
Size of perforations 1/4 in. by 3/8 in.
60 perforations from 120 ft. to 126 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
gal./min. with ft. drawdown after hrs.
" " " "
" " " "
Bailer test 30 gal./min. with 5 ft. drawdown after 1 hrs.
Artesian flow g.p.m.
Temperature of water 51 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 16 sacks
How was cement grout placed? TOP

Was a drive shoe used? ☒ Yes ☐ No Plugs 1 Size: location 138 ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number
NE 1/4 NE 1/4 Section 18 T. 55 R. 24 W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 40 ft.
Static level 64 ft. below land surface. Date 7-13-78
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing -

Depth drilled 145 ft. Depth of completed well 145 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil, Sandy loam	0	4	
Silt, Brown	4	12	
Clay, Blue Grey	12	40	
Silt, Brown	40	41	30
Cement Gravel	41	83	
Clay Grey	83	98	
Clay Blue	98	101	
Sand, Fine, Heaving	101	110	64
Sandstone	110	117	
Gravel w/ sand	117	128	64
Silt Grey	128	139	
Clay Grey	139	143	
Gravel, very fine sand	143	145	

Gravel was Packed in well from 138 to 145, not cemented, to form a plug

Work started 7-12- 1978 Completed 7-24- 1978
Date well drilling machine moved off of well 7-24- 1978

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Richard Beck Date 7-25- 1978
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1200

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name John W. Beck Well Drilling
(Person, firm or corporation) (Type or print)

Address 24137 3, 9 Kyleme Dr Conby Ore

[Signed] John W. Beck
(Water Well Contractor)

Contractor's License No. 449 Date 7-25, 1978

(USE ADDITIONAL SHEETS IF NECESSARY)